Vanguard Renewables Waupaca AD1

Brooks Farms Dairy LLC Waupaca County, WI February 2023



Prepared by:

MSA Professional Services 1230 South Boulevard Baraboo, WI 53913 Phone: +1 (608) 356-2771 www.msa-ps.com

Project No. 21720000

© February 2023 MSA Professional Services, Inc.



Vanguard Renewables Waupaca AD1 Brooks Farms Dairy LLC

TABLE OF CONTENTS

п

<u>- 030</u>
EXECUTIVE SUMMARY
CHAPTER 1 – Project Description
1.1 Introduction 1
1.2 Design Objective 1
1.3 Project Responsibilities
1.4 Construction Timeline
CHAPTER 2 – Site Assessment
2.1 Topography
2.2 Soils Investigation 4
2.3 Wells
2.4 Susceptible Areas 6
CHAPTER 3 – Improvement Descriptions
3.1 Hydrolysis Tanks
3.2 Digesters and Gas Upgrading System
3.3 Feed Storage Runoff Controls
3.4 Waste Storage Facility – Permeate Tank
3.5 Sand Separation System and Associated Transfers
3.6 VSEP and Solids Building9
3.7 Stormwater Considerations
3.8 Safety Features
3.9 Failure Analyses
3.10 NRCS 634 Variance Request11
CHAPTER 4 – Management Assessment
4.1 Waste Generation
4.2 Waste Management
4.3 Digester Management
4.4 Sand Separation Management14
CHAPTER 5 – Design Standards and Specifications
5.1 NRCS Conservation Practice Standards
5.2 Additional Design Requirements
5.3 Construction Specifications
CHAPTER 6 – Authority 16

LIST OF TABLES

Table 1.	Project Responsibilities	· · · · · · · · · · · · · · · · · · ·	2
----------	--------------------------	---------------------------------------	---

LIST OF APPENDICES

- **APPENDIX A** Construction Plans
- APPENDIX B Maps
- APPENDIX C Soil Logs and Geotechnical Investigation APPENDIX D Operation & Maintenance Plan
- APPENDIX E Quality Assurance Plan
- APPENDIX F Calculations
- APPENDIX G Wetland Delineation Documentation
- APPENDIX H Digester and Hydrolysis Tanks Documentation

EXECUTIVE SUMMARY

Brooks Farms Dairy is working with Vanguard Renewables who is proposing to add two anaerobic digesters to the operation prior to sending their manure to long term storage. Part of this plan includes adding sand separation and the needed manure transfer systems, nutrient concentration systems, solids storage, feed storage runoff collection, an additional long-term waste storage facility, and a permanent manure pipeline running to the south. The following report discusses these improvements. While the digesters will be managed by a third party, all waste will be managed under the Farm's WPDES CAFO permit. Animal numbers are not proposed to increase and the digester will be processing food waste which will be managed under the Farm's WPDES permit.

This design will impact days of storage by adding offsite waste, adding an additional long-term storage, adding feed storage leachate and runoff, and removing sand bedding from the waste stream.

A permit modification is required for the additional facilities and sample points as well as the addition of waste and will follow the submittal of the design plans.

The Waupaca AD1 facility is a proposed renewable natural gas production facility located at N1757 County Road A, Waupaca, WI which will produce renewable natural gas from the anaerobic digestion of manure and food waste.

Liquid food waste materials will be brought to the facility by truck and may be unloaded directly into one of the hydrolysis tanks. Food waste materials in packaging containers may also be brought onsite by truck and unloaded within an enclosed organics receiving area (ORA) building. Within the ORA, packaged food waste will be separated from the packaging materials and the food waste will be directed to one of the hydrolysis tanks. The hydrolysis tanks will screen for inorganic material which will then be collected and sent offsite for waste disposal. The packaging materials will be compacted and sent offsite for waste disposal or recycled if possible.

The daily amount of food waste received is anticipated to be approximately 225 tons per day. Onsite storage time for the food waste materials will be minimal because the anaerobic digester will require food waste materials to be fed continuously while the digester is in operation. Less than half of the material fed to the anaerobic digester will be comprised of manure from the adjacent Brooks Farms Dairy and more than half will be comprised of food waste materials.

For the purposes of this Report, the terminology "food waste" and "organics" may be used interchangeably and are intended to have the same meaning.

CHAPTER 1 – PROJECT DESCRIPTION

1.1 INTRODUCTION

This design report has been prepared to outline the design work for construction of a sand separation facility, anaerobic digester facility, solids separation and nutrient concentration system (VSEP), and associated transfer tanks and piping. The Farm is an existing dairy operation that operates under Wisconsin Pollutant Discharge Elimination System (WPDES) Permit No. 0066885. The Farm has entered into an agreement with Vanguard Renewables. (hereafter Vanguard) to allow Vanguard to process the dairy manure and food waste to produce pipeline-quality renewable natural gas (RNG). The Farm is located at N1757 County Road A, Waupaca, Town of Lind, Waupaca County, Wisconsin. The Farm is owned and operated by the Brooks family.

1.2 DESIGN OBJECTIVE

The purpose of the proposed project is to utilize food waste otherwise destined for a landfill, create a byproduct with more plant available nutrients than raw manure, and generate pipeline-quality renewable natural gas (RNG) through the anaerobic digestion of dairy manure and food waste. The components of the project are a waste transfer system with tanks and pipelines, a sand separation system, food waste receiving structures, two in ground digesters, a solids separation system, a nutrient concentration system (VSEP), biogas upgrading equipment and associated equipment enclosures, and a utility interconnect. The project does not include new or expanded facilities for livestock or expand the herd size. The proposed project consists of the following:

- Feed storage runoff collection and transfer to permeate tank
- Manure transfer from existing barns to sand separation system
- Sand separation building with tanks and process equipment
- Organics receiving area for offsite wastes (non-reviewable)
- Three hydrolysis tanks before the digesters
- Two below ground, 1,780,000-gallon anaerobic digester (AD) tanks
- Solids separation system
- VSEP nutrient concentration system with buffer tank
- Permeate tank (proposed long term waste storage facility)
- Concentrate transfer system to existing waste storage facility
- Associated transfer piping
- H2S removal
- Utility Interconnect
- Access roads
- Stormwater Improvements
- Permanent manure pipeline to southern fields

The purpose of this design report and associated construction drawings is to provide sufficient detail to construct the following components:

- Construction of two belowground, 1,780,000-gallon anaerobic digester (AD) tanks compliant with NRCS 313 and 522, designed to ACI 350.
- Construction of three reception tanks called hydrolysis tanks, compliant with NRCS 634, designed to ACI 350.

- Construction of leachate and runoff transfer systems (gravity and forcemain) compliant with NRCS 634 and NRCS 561.
- Construction of a long-term waste storage facility tank (Permeate Tank) compliant with NRCS 313 and 522, designed to ACI 318.
- Construction of a sand separation system compliant with NRCS 634.
- Construction of all associated transfer systems compliant with NRCS 634.
- Construction of manure solids storage to NRCS 313.

1.3 PROJECT RESPONSIBILITIES

This project involves multiple firms, with each firm responsible for design and certification of the items as outlined in the following table.

	DESIGN	
DESCRIPTION	RESPONSIBILITY	VENDOR
Manure Transfer from Existing Barns to Sand Separation	MSA	Komro
Manure Sand Separation Civil and Structural Design	MSA	Komro
Permanent Manure Pipeline from Farm Design	MSA	
Feed Storage Runoff Collection and Piping to Permeate Tank	MSA	
Hydrolysis Tanks Structural Design	PlanET/MPE	PlanET
Receiving Pumps Technical Container Structural	PlanET/MPE	PlanET
Anerobic Digester Structural Design	PlanET/MPE	PlanET
Digester Facility Site Civil	USM/MSA	
	Ross	
	Engineering/Purpose	
Overall Site Layout	Engineering	
	Ross	
	Engineering/Purpose	
Raw Gas Piping Design	Engineering	
H2S Removal and Upgrading Structural and Building Design	PlanET/MPE	PlanET
	Ross	
Disease Disting Design to Utility Internet	Engineering/Purpose	
Biogas Piping Design to Utility Interconnect	Engineering	
	ROSS	
Digestate Pining Design to Solids Separation	Engineering	
SW/ECO Egged Tank Structural Design	мсл	
SWLCO TEEd Talk Structural Design	Ross	
	Engineering/Purnose	
Solids Separation Building and Structural Design	Engineering	
	Ross	
	Engineering/Purpose	
VSEP Building and Structural Design	Engineering	
	Ross	
VSEP System Design	Engineering/Purpose	New Logic Research

Table 1. Project Responsibilities

	Engineering
	Ross
	Engineering/Purpose
Permeate Piping Design to Organics Receiving Area	Engineering
	Ross
	Engineering/Purpose
Permeate Piping Design to Permeate Tank	Engineering
	Ross
	Engineering/Purpose
Concentrate Piping Design to Concentrate Lagoon	Engineering
Permeate Tank Civil and Structural Design	MSA

1.4 CONSTRUCTION TIMELINE

- Start of Construction/Site Mobilization: April 3, 2023
- Anerobic Digester Tank (Start Excavation): May 1, 2023
- Sand Separation (Start Excavation): May 1, 2023
- Nutrient Recovery System (Start Excavation): June 26, 2023

CHAPTER 2 – SITE ASSESSMENT

2.1 TOPOGRAPHY

The existing topography was determined using survey of the site provided by MSA Professional Services and Westwood in 2022. The result of the topographic survey is included in the construction drawings in **Appendix A**.

2.2 SOILS INVESTIGATION

In 2022, four iterations of soils investigations were completed at the Farm. Preliminary geotech soil borings (ST1 through ST5) were completed by Braun Intertec on April 27. Braun Intertec did additional soil borings (ST6 through ST19) on November 9. On November 17, Geosyntec Consultants completed soil borings B-1 through B-12. Dale Mitte of MSA completed test pits with a tracked backhoe on November 8; due to a staking issue, these are numbered oddly, as 2022-2, 3, 5, 8, 10, 16, 17, and 18. There are no additional or missing test pits. The controlling elevations are all based off of water observed in soils investigations. For the Permeate Tank, that water was in ST13, at elevation 821.7. For the Digesters, the controlling elevation is 820.07 in ST4, and for the hydrolysis tanks, the controlling elevation is 820.0 in B6.

Geosyntec borings B7 and B12 showed unusually high water that was only visible in these two borings, and none of the surrounding borings. The following is a discussion on these borings and why these water levels are not used as the limiting water elevations, from Dale Mitte, soil scientist and Andrew Skwor, PE.

"In B7, the log notes that in the yellowish, red sandy silty clay there was trace interspersed fine gravel mixed in the material. Mostly likely when drilled they encountered a somewhat gravelly-sand pocket in the CL till. These gravelly-sand pockets with their open void spaces sometimes hold free water in them and when punctured will have water drain out freely. This water cannot readily migrate downward in the SP sand layer as the CL till material around it is less permeable by a significant amount. The water in B7 is shown at elevation 824.5'. ST6 is right next to it and is typical of most of the pits and logs right beside B7 and it does not have water in the CL till, but like almost all other borings the water is down in the sand layer below.

ST6 has no water above elevation 818.0', it has water under elevation 818.0' or 12.5' deep not 5 ft deep. The sand in B7 is at elevation 818.2' or 11.3' deep with water seeping out above it but would have been difficult to tell actual water levels in the SP sand below.

Also note B6, B7, and ST6, ST7 are all close together and B6, B7, and ST6 are very similar with topsoil over CL glacial till over SP sand with the water listed in the sand. The CL till layer is 8.5' to 11.3' deep. Overall, in the logs and also what was observed in the excavated test pits is that the CL red glacial till does contain some sandy pockets. The sand pockets in the CL till of the excavated test pits did not have observed water per the logs which is a majority of noted logs by both drilling firms.

B12 and ST 13 are located in the waterway/drainageway from the wetland location to the northwest. Observed no water initially drilling in B12 until 16' (elevation 812.0) when they encountered the SW sand. After 24 hrs the water observation was at 16'. The CL till above

notes silty clay with trace of coarse sand. This boring,ST13, and ST10 have the CL glacial till layer as thicker in the area running 16' plus of CL glacial till, whereas most of the other borings and test pits, the CL glacial till is 9' to 12' thick on average.

To summarize B12 and ST13 have a thicker till layer, thus more weight pushing down on the SP layer with water. Once the layer is punctured by drilling the pressure of the extra weight is relieved and pushes water upwards.

In ST13, at the start of the boring no water was observed, but after 30-minutes water was at 6.5'. This log is the only one listingtopsoil over SC till to 7.5' and the CH fill to 16.5' plus. No water was observed at the start and no SP sand was found at least to 16.5'. But after 30-minutes they had water at 6.5'. An assumption is the SC till which is sandier than the CH fill may had a small seep or wet lenses which after a few minutes found its way over to the newly drilled boring and filled it. The sand pockets in the tills may contain water but can be emptied and also the site can be assisted by drain tile with proper drain fill. The tile and drain fill will take away those upper perched lenses andpockets and also relieve that upper weight pressure which would stabilize over time

ST10 does somewhat the same, no sand for 6.5' and no water until auger was removed, the water was recorded to 12.5'.

Please note in B8 the water was recorded at 13.5' at the start which was the top of the SP sand, then in 15 hrs later it was 8.4'. In 24 hrs it was back down to 11 ft. In my professional opinion, the pressure pushes the water below in the SP sand layer up slowly but then once it stabilizes the water would go back down to the SP layer. This was recognized in the test pits where the water was originally observed around 16.5' to 18' in SB8 and SB10, but upon checking later on during the same day the water came up to around 13', but stayed in the SP layer depth. For almost all of the borings of both geotechnical firms, the logs noted the water in the SP layer mostly and not much in the CL till layer.

In my professional opinion, the actual water table is in the SP sand layer and at the top of the SP sand layer or somewhat below it by 1-3'. Everything about the SP sand layer is perched or happened by temporarily relieving the pressure by borings. Notes most of the observed water is down in the SP sand layer and is between 812 to 820 elevation. This also fits the noted geotechnical firms logs and Natural History Tech Report 007.

Also, the two well logs including one from 2020 shows water being stable in depth of 10'-18' down but back both are just in the SP sand layer, not above into the clay layer

Observed/recorded water at 3.7'. There is no note about overnight weather or any site conditions that would be contributed to the water level change. Also, this hole was drilled on 11/16/22. It was one of the first holes, would have been nice if left open for a few more days to recheck as they drilled from 11/16 to 11/19 on Saturday according to the logs. So now there were more borings done over the area which would assist in relieving the pressure. IE why the water in B8 on 11/17/22 came up to 8.4' but was already going back down to 11' in 24 hours."

2.3 WELLS

The Farm has four wells onsite. Contamination from surface runoff and risk from traffic damage is minimal, due to the proximity of the wells to the facilities and motor vehicle traffic. The locations of the wells can be seen in **Appendix A**. The wells are all outside of 250' of the proposed infrastructure. Three wells (Unique well IDs UN280, ZG695, and NP653) are within 245', 165', and 115' of the existing feed storage (FSA) respectively, and 185', 230', and 200' of the Small Pit, respectively, which will be collecting runoff from the FSA. These distances are greater than the distances required by NR812. The proposed piping for the feed storage collection is not within 250' of the wells. In addition, there are no community wells located within 1,000' of the proposed waste storage facilities.

2.4 SUSCEPTIBLE AREAS

The site was evaluated for susceptible features such as karst features, surface water features, and drain tiles. A delineated wetland is located directly north of the proposed digester facilities. Wetland indicator soils are present, though the delineation let to only the northern wetland being identified in the immediate parcel. The county requires a 25' setback to the wetland boundary. No bedrock was discovered in any of the soil investigations, though groundwater was present in several (see section 2.2 for a more in depth discussion). There are no existing field tile drains in the area of the proposed improvements. There are no floodplains within 1,000 ft of the proposed improvements, per WI DNR SWDV. No wetlands or water bodies have been or will be filled as a result of construction activities or digester facility operations. The Farm is pursuing a clean water discharge permit which is not included in this submittal.

CHAPTER 3 – IMPROVEMENT DESCRIPTIONS

3.1 HYDROLYSIS TANKS

Three hydrolysis tanks are proposed to feed the digesters. The purpose of the hydrolysis tanks is to take the manure after sand has been removed and to take food waste from the Organics Receiving Area (ORA) and combine them prior to addition to the digester. These tanks will also serve as a final step for removing any material that would be detrimental to the digester that did not get removed at the ORA or in the sand separation system. Hydrolysis Tank 1 (#HT1) will hold high organics liquids (FOG), while Hydrolysis Tanks 2 and 3 (#HT2 and #HT3, respectively) will hold manure and clean organics.

#HT1 receives high organics liquids from trucks unloading clean liquids through the Technical Container #1 (#TC1). #HT2 and #HT3 can receive clean organics from the ORA, through underground piping, or from unloading trucks, through the #TC1. They receive manure through underground piping from the proposed sand separation building. While #HT2 or #HT3 is being filled, it is recirculated through the hydrocyclone in the Technical Container #2 (#TC2). While this is happening, the other tank (#HT2 or #HT3, the one that has already been filled before), is feeding the digesters. The content in #HT1 will be fed into the digesters together with #HT2 and #HT3 at a lower rate, varying accordingly to the required organic load. In case it is required, there will be available piping for by-passing the hydrolysis tanks, sending manure from the sand separation building, or organics from the ORA or the trucks' unloading bay straight to the digesters. Also, liquid organics can be sent from #HT1 to the ORA in order to dilute high solids organics while diminishing the use of water.

The tanks all have interior diameters of 45'-11" and 12" thick walls. Tank 1 has a wall height of 14'-10" with a maximum liquid depth of 8'-9". Tanks 2 and 3 have wall heights of 26'-3" with maximum liquid depths of 25'. The volume of Hydrolysis Tank 1 is 108,000 gallons, while the volumes of Hydrolysis Tanks 2 and 3 are 309,000 gallons each. The slabs of each of the hydrolysis tanks is set at 824.0, and the proposed grade outside of the tanks ranges from 829.0 to 831.0. The hydrolysis tanks are designed to NRCS 634 Waste Transfer (11/2022), with concrete designed to ACI 350. This design requires a minimum of 2' to subsurface saturation, and the hydrolysis tanks have 4.0' of separation, with water at 820.0' in soils investigation B6. Bedrock was not encountered in any of the soils investigations; the required 2' of separation is met.

3.2 DIGESTERS AND GAS UPGRADING SYSTEM

Two anaerobic digesters are proposed as part of the project. The waste stream will be pump from the hydrolysis tanks to the digester. From the digesters, the digestate will move to the solids separation and V-SEP building before going to long-term waste storage in the existing waste storage (Concentrate Storage) and the proposed waste storage (Permeate Tank). The digesters are mesophilic in configuration with a required operation temperature of 100.4 degrees F. Heat is supplied by hot water recirculation, external heat exchangers and a fuel gas fired hot water boiler. There are three side mounted agitators and two submerged mixers in each digester. Over/under pressure relief valves are to be installed on the digesters.

The gas upgrading system consists of the following steps:

1. Gas conditioning: The gas is collected into a raw gas buffer tank of 2,642 gallons. Then it is cooled through two cold water chillers and the liquid faction is separated.

- 2. Filtration: The gas is filtered through a PSA system (6 PSA Adsorber vessels), plus 2 H₂S carbon filters and 1 VOC carbon filter.
- 3. Gas compression: The biomethane is collected in a Biomethane Buffer tank and then sent through one of the two in-parallel blowers to the interface with the customer.

The digesters each have an interior diameter of 111.6' with 16" thick walls, with a concrete wall height of 26'-5" and a roof height on top of the wall of 18'-1/2", for a total height of 44'-5 $\frac{1}{2}$ ". The maximum liquid depth in the digesters is 24'-4", which correlates to a maximum volume of 1,780,000 gallons in each digester. The digester slab is proposed to be at elevation 824.5, sloping at 2% to the middle to an elevation of 823.38, sitting 10' below proposed grade. The digesters are designed to ACI 350 liquid tight concrete with waterstop, Table 3, Column A of NRCS 522 Pond Sealing and Lining (06/2021). Due to the ACI 350 design, the digesters do not require a subliner. This design requires a minimum of 2' to subsurface saturation, and the digesters have 3.3' of separation, with water at 820.1' in soils investigation ST4. Bedrock was not encountered in any of the soils investigations; the required 1.5' of separation is met.

3.3 FEED STORAGE RUNOFF CONTROLS

The Farm's existing feed storage system does not have runoff controls. The majority of runoff flows to the south, though the apron on the north side of the bunkers flows north. Any apron runoff from the eastern two bunkers flows to the Small Pit. A collection system is proposed for the south side of the bunkers at the low spot where runoff leaves the existing feed pad apron, with a gravity pipe running to the west, to circle around to the north of the bunkers and penetrate the Small Pit. The proposed catch basin is a 4' x 4' square manhole x 5' deep with a Neenah R-4482A grate (34" x 34"), with a 24" corrugated HDPE pipe at 0.16% slope. From the Small Pit, the runoff will be pumped with a Wilo submersible pump through 10" DR17 HDPE to the new waste storage facility (Permeate Tank).

3.4 WASTE STORAGE FACILITY – PERMEATE TANK

A new waste storage facility is proposed south of the existing waste storage facility. The existing waste storage is proposed to be used for housing the "concentrate" portion of the waste stream (the portion of waste from the V-SEP that has the majority of the nutrients in it, and the proposed Permeate Tank will hold the permeate or tea water portion, which will be a diluted, low nutrient concentration waste stream. The proposed storage is a rectangular vertical walled concrete tank measuring 230' x 470' inside dimensions x 16' deep, with a bottom elevation at 825.0. The storage facility will be constructed of Reduced Seepage Concrete with Waterstop (NRCS 522 Table 2, Column A) and a 1.5' thick subliner with soils meeting P200>20% and PI>7 (NRCS 522 Table 2A, Column A). The storage will be holding process wastewater and is proposed to meet WI Admin. Code NR 213 through NR 213.06 Alternative Designs, as the storage is designed to NRCS standards more stringent than Chapter NR 213. The storage is sized for 10.7 million gallons of MOL volume; between all storages onsite, the Farm will have nearly 18.5 million gallons of storage or 222 days of storage at their existing animal numbers. In depth storage calculations are available in Appendix F. This design requires a minimum of 2.5' to subsurface saturation, and the Permeate Tank has 3.3' of separation, with water at 821.7' in soils investigation ST13. Bedrock was not encountered in any of the soils investigations; the required 1.5' of separation is met. The eastern wall of the storage is designed for

3.5 SAND SEPARATION SYSTEM AND ASSOCIATED TRANSFERS

The following description is to aid in understanding how sand laden manure is processed and is transferred through the system before the digester system. The various plansets in **Appendix A** should be referenced for specific pipe sizes and materials as well as pump models.

The current manure transfer in the Freestall Barn is an auger channel that runs to the north to a two cell reception tank before being pumped to the Big Pit. This will be modified as part of the sand separation system. The auger will be reversed, and a 5' deep, 11.33' wide by 30' long flush tank is proposed at the southern end of the channel. A 24" ADS gravity flume is proposed to move sand laden manure from the tank to the sand building. A 12" DR17 HPDE flush line will loop back to the tank. The existing reception tank in the freestall barn will be left in place with the option of pumping directly to the manure storage if the sand building is ever not operational.

Heifers are also bedded on sand at the Farm in the Heifer Barn directly south of the Freestall Barn; their manure is currently scraped to the west end of the barn and then to the south directly into the big pit. A flush flume is proposed on the west end just outside of the existing barn to run to the north, joining the freestall barn flume; the barn will be extended over the proposed flume (by others). A 12" DR17 HDPE flush line will come from the sand building to the 24" ADS gravity flume. The scrape alley will remain in place, though concrete will need to be replaced and an overhead door is required on the south end of the barn extension.

The sand separation system is provided by Komro Sales and Services, Inc. When manure enters the sand separation system it will go through a cross auger and sand settling lanes. The sand will be washed and stored within the sand building. Manure and the water used to wash the sand will then be discharged to the hydrolysis tanks after passing through a piping manifold in Technical Container 1.

The sand separation system will also have the option of discharging directly to the manure storage without going through digestion. The first bypass line is proposed to tie into the existing freestall transfer line. A second bypass line is proposed around the western side of the manure storage to discharge over the top.

3.6 VSEP AND SOLIDS BUILDING

The following description is to aid in understanding how digested manure is processed and is transferred through the system before long term storage. The various plansets in **Appendix A** should be referenced for specific pipe sizes and materials as well as pump models. A watertight concrete building (plans available in **Appendix A**) is proposed to the south of the existing lagoon and between the digesters and the proposed permeate waste storage tank. This building will have a solids separation and stacking area on the west side, with a pressate feed tank (TK7005 SWECO Feed Tank) measuring 11.33' x 47' x 12' deep to the north of the stacking building. The solids separation and stacking area of the building is roofed with a 6' wall and open to the air. The SWECO feed tank is north of the 6' wall, though still roofed. The solids stacking area is proposed to be concrete with waterstop, though it is also proposed to have 1.5' of P200>30% and PI > 5 liner soils beneath to meet NRCS CPS 313 Table 5, Roofed Working Surface Stacking Area. Digested manure is fed through an above ground insulated and heat traced Line 32 and pumped into the solids separator screw press (Boerger RC40) located in a mezzanine above, which drops solids to the floor below. Pressate liquid is routed through a gravity line to the SWECO feed tank; there is

also a floor drain from the mezzanine that ties into this gravity line (these lines will be insulated and heat traced). There is a floor drain in the south end of the solids stacking area that leads to a 6' deep x 4' diameter manhole TK-7071, which then pumps to the drain manifold in the VSEP portion of the building. From the SWECO feed tank, the pressate is pumped into the SWECOs which are located in the VSEP building. The SWECOs are another layer of solids separation, the solid fraction of which ends up back in the solids stacking area. The VSEP side of the building is not open to the exterior and is also concrete with waterstop. Within the VSEP building, the liquid from the SWECOs goes through the VSEP to be divided into two waste streams: concentrate and permeate. As their names suggest, this is a nutrient concentration system to help with better nutrient management. The VSEP discharges permeate through Line 50 to TK-7062, another 4' diameter x 6' deep manhole. This is pumped via surface mounted pump through above ground piping, splitting to Line 42 (heading back to the ORA) and Line 43, which goes to the proposed permeate waste storage facility. Line 42 has a tee to Line 53, which is stubbed for future use. The VSEP also discharges CIP permeate through Line 51 to TK-7073, and CIP concentrate through Line 51 to TK-7074 (both TK structures are 4' diameter x 6' deep manholes). Both manholes use submersible pumps to pump to the drain manifold. The drain manifold pumps permeate through Line 44 to the proposed permeate storage tank and concentrate through Line 45 to the existing waste storage facility. The floor of the VSEP has floor drains which lead to TK-7072 (4' diameter x 6' deep manhole), which pumps to the drain manifold; a drain from the VSEP itself (Line 41) also enters these drains.

3.7 STORMWATER CONSIDERATIONS

To prevent issues with stormwater flow and to keep the site drained, the site has been graded to drain away from structures and to the wetland. Several surface inlets and culverts are proposed. Any pipes crossing under a stormwater pipe within 3' will be insulated in the area of the crossing.

3.8 SAFETY FEATURES

Safety considerations have been made for each of the structures onsite. The manhole outside of the freestall will be covered to prevent entry. The proposed waste storage facility will have a fence with warning signs installed at any point the top of wall is less than 5' above grade. The feed storage inlet will have a grate over the top, and the Small Pit will have gates installed across the ramp. The digesters and hydrolysis tanks are completely covered and will have confined space warning signs at any access points.

The facility will have appropriate road marking and floor signage/painting (using appropriate wear resistant colors) to designate segregation, process, safety, hazard, and storage areas. Facility floors will be pitched toward drains but be level enough for safe forklift operation. Floor surfaces will have appropriate texture to prevent slipping, spinning wheels of equipment such as forklifts. Air curtains will be installed to control fugitive odor release when doors are open only on the two bunker unloading doors. Gully/Drains covered by grating on the inside of the door threshold to prevent liquid from escaping the building. The HVAC/odor control system will include air circulation to all areas/pits and sumps to prevent hazardous gas/condensation/odor pockets forming to the pit, or free-standing fans to reduce mold growth.

Alarms will be installed to warn Operations before an overflow event, as well as a transparent access window, with the ability to be in-situ cleaned (i.e., mounted squidgy), for visual awareness of Tank levels. Emergency overflow will be included. Over/under pressure relief valves are to be installed on the digesters.

3.9 FAILURE ANALYSES

Failure of the waste storage (permeate) tank is unlikely due to its entire construction of reinforced concrete. The most logical scenario in which waste would leave structure would be improper operation and maintenance causing the storage to overtop. If it were to overtop, waste would flow 130' until reaching a classified wetland, and additional 430' until reaching an unnamed intermittent stream (WBIC 5021201). This stream is an eventual tributary of Walla Walla Creek (WBIC 254000) after 7,200'. At the point of discovering a storage has overtopped, the owner shall gather big square or round bales and place in front of waste flow, if possible, to create a dam. Additionally, a soil dam could be created to stem the flow of contaminated water. Once the waste flow is stopped, the Farm would notify the DNR and proper authorities, and begin the cleanup process.

In the digester design, worst-case conditions were run separately in addition to the conditions associated with the use of the Environmental Endurance Factor 'Sd' in ACI350, which all provides a high degree of safety and confidence against catastrophic failure. In addition to the water-tight design, there will also be an interior liner to completely enclose the fluid within, providing a high degree of confidence that no leaks will occur.

In the event the digester is offline, the farm has two backup lines to transfer from the sand separation into the existing waste storage facility, as well as the option to pump sand laden manure directly to the waste storage facility from the freestall barn and scrape heifer manure directly to the waste storage if the sand separation system is offline.

3.10 NRCS 634 VARIANCE REQUEST

On behalf of Brooks Farms (Permittee) and Vanguard Renewables, we are requesting a variance to Wisconsin NRCS Conservation Practice Standard Code 634 Waste Transfer, November 2022. This consideration is for piping systems beyond or downstream of Technical Container #1 (TC#1). TC#1 is the point at which yard piping (true waste transfer systems) transitions to process piping. The variance is being requested because some of the process piping does not meet the required 3 feet per second velocity within in the standard. Additionally, the plant designer, PlanET Biogas, uses a volume-based operation philosophy and feeding schedule which would need to change; maintaining 3 fps would result in pipe size changes which would result in flowrate changes. Because of their experience, number of plants developed as well as plant successes, it was determined their recommendations on pipe size and pumps needed to be followed as closely as possible.

The minimal pipeline velocity within the standard is to minimize solid settlement and control various piping and pump issues long-term. In the case of this project several features have been added to reduce solid size thus making them less prone to settling and staying within the flow. Some of those features include:

- Bar screen placed at the influent to the sand separation system.
- Cross gutter and settling lanes within the sand separation building which create settlement and carry organic solids out of the waste stream as well as create pockets of floating debris which can get skimmed off.
- The discharge tank within the sand separation system pumps to TC#1 uses a pump and maceration system to reduce size of solids to the digestion process. The pump and macerater are used in conjunction with the agitator in the tank to allow recirculation which homogenizes the waste and reduces the chance of passing large solids.

• Once comingled with food waste, a hydrocyclone is utilized as the initial process to catch remaining sand particles and debris before being pushed into the digestion process.

Finally, management of the process is another key part to making sure the system stays operational. Vanguard Renewables has a management program to staff the facility 6 days per week with on-call staff during off hours. The system also has various controls including flow meters, amperage monitoring, and pressure sensors throughout the system to note when there may be a pipe restriction or blockage. Maintenance is completed using pipeline management Standard Operation Procedures (SOP) which may include backflushing, jetting, vacuuming, or section replacement. The system design also has strategic redundancy which allows pipelines to be taken offline for maintenance to minimize disruption of the process.

Andrew Skwor, PE had a phone discussion with Mr. Bernie Michaud, on February 16th, 2023 at approximately 10:15am regarding pipeline and flow velocity for the process system. Mr. Michaud was very supportive of the conversation, but also provided concerns that we feel we address within our request. Based on that conversation is how we deemed a variance request to the standard was an appropriate action.

For reasoning stated we feel the variance request is justified and appreciate the consideration to grant the variance for this project.

CHAPTER 4 – MANAGEMENT ASSESSMENT

4.1 WASTE GENERATION

The manure on the dairy is currently all directed towards the Big Pit, which will be converted to use as a Concentrate Storage. Cows, heifers, and calves are housed in various buildings onsite; the main freestall barn is the one in question for this design. Cows are bedded on sand, which is currently being directed to the manure storage. The Farm will start separating sand out of the manure and recycling it as part of the proposed improvements. The proposed improvements tie into the existing waste handling system. The proposed changes add additional waste to the waste stream, as well as adding storage volume. The proposed improvements have been designed assuming 285 tons per day of offsite waste being imported onto the farm (19,079,468 gallons), though the operation point of the system is 225 tons per day of offsite waste, which correlates to approximately 15,000,000 gallons annually of offsite waste.

The farm will have 222 days of storage when the improvements are complete if the digester is bringing in the full capacity of off-site waste, with 9,274,741 gallons annually of manure and process wastewater, and a maximum design of 19,079,468 gallons annually of off-site waste. Approximately 953,973 gallons of volume is to be removed through the solids separation screw press prior to the V-SEP. It is estimated that 5% of the volume of the waste will be removed as solids, and this estimated volume is based solely on the maximum offsite waste volume. The total storage volumes on the farm will be 18,495,540 gallons between the current "Big Pit" waste storage facility and the proposed permeate waste storage facility. It should be noted that these volumes and the days of storage are the maximum capacity of the digester system, not the proposed operating point of the digester.

4.2 WASTE MANAGEMENT

The Farm is responsible for all facilities, equipment, and piping to the final tank in the sand separation building and from the long term waste storages (Big Pit/Concentrate Storage and Permeate Tank) to the nutrient's end use or when it is sold. Farm personnel are required to operate, manage, and maintain all facilities of this transfer system including the sand separation system.

Vanguard staff will be responsible for the facility and equipment downstream of the final tank in the sand separation building. Vanguard personnel are required to operate, manage, and maintain all facilities of the transfer system, anerobic digesters, and digester recirculation.

The sand separation system, once optimized, will remove a minimum of 97% of the sand from the waste stream and require only daily maintenance per the vendor's operation and maintenance plan and schedule.

The entire system is minimally influenced by weather as all critical equipment is housed and capable of being heated. This will allow weather influences to be greatly reduced on component wear and maintenance to reduce risk and create better longevity.

The Farm is aware that the nutrients brought into their permit will exceed what their acreage can currently have applied. The farm is discussing options, including but not limited to selling the additional nutrients that Vanguard is bringing into the digesters. To do so the Farm would be

required to have a commercial fertilizer license from DATCP. The agreement between Vanguard and the Farm states that the Farm's nutrient management plan will not be exceeded.

4.3 DIGESTER MANAGEMENT

The proposed project site is adjacent to the dairy facility and set back from the nearest road. The majority of piping is underground. This proposed project should not change the overall aesthetics of the Farm. The surrounding area is a rural farming community, with several rural residences scattered in the area. There should be no negative impact to aesthetics of the area with the proposed project.

The digester will be operated to ensure liquid level is maintained in the operating band, manure temperature is kept at approximately 100.4 degrees F, and gas pressure is maintained within the design specifications for the tank. All components of the digester will be maintained in accordance with manufacturer's recommendations.

4.4 SAND SEPARATION MANAGEMENT

While the Farm will be responsible for the operation of the sand separation, the digester developer will be operating the transfer of manure into the hydrolysis tanks and therefore into the digesters. The digester operation and mass balance has been sized such that the digester system will always be available to take manure. In the event the digester is offline, the farm has two backup lines to transfer into the existing waste storage facility, as well as the option to pump sand laden manure directly to the waste storage facility from the freestall barn and scrape heifer manure directly to the waste storage.

Brooks Farms Dairy Llc, Waupaca County, Wi

CHAPTER 5 – DESIGN STANDARDS AND SPECIFICATIONS

5.1 NRCS CONSERVATION PRACTICE STANDARDS

The following NRCS Conservation Practices standards are the applicable standards used in this design:

- Wisconsin USDA-NRCS Conservation Practice Standard (CPS) 313 Waste Storage Facility (10/2017R)
- Wisconsin USDA NRCS CPS 366 Anaerobic Digester (01/2018)
- Wisconsin USDA-NRCS CPS 522 Pond Sealing & Lining Concrete (06/2021)
- Wisconsin USDA-NRCS CPS 533 Pumping Plant (08/2021)
- Wisconsin USDA-NRCS CPS 561 Heavy Use Area Protection (11/2022)
- Wisconsin USDA-NRCS CPS 634 Waste Transfer (11/2022)

5.2 ADDITIONAL DESIGN REQUIREMENTS

- Wisconsin Administrative Code NR 243
- Wisconsin Administrative Code NR 213
- American Concrete Institute (ACI) Code 350-20: Code Requirements for Environmental Engineering Concrete Structures (for Digesters)
- ACI Code 318-19: Building Code Requirements for Structural Concrete (for all other structural concrete)

5.3 CONSTRUCTION SPECIFICATIONS

The following construction specifications shall be used for the completion of this work:

- USDA-NRCS Wisconsin 2. Excavation (5/18)
- USDA NRCS Wisconsin 3. Earthfill (5/22)
- USDA-NRCS Wisconsin 4. Concrete (11/22)
- USDA-NRCS Wisconsin 004. WS Embedded or Expansive Waterstop (11/22)
- USDA-NRCS Wisconsin 204. Earthfill for Waste Storage Facilities (9/18)
- USDA-NRCS Wisconsin 300. Clay Liner (4/18)
- USDA-NRCS Wisconsin 634. Waste Transfer Pipe (11/22)
- WDNR CPS 1053 Channel Erosion Matt (11/2018)
- WDNR CPS 1056 Silt Fence (3/2006)
- WDNR CPS 1057 Trackout Control Practices (7/2018)
- WDNR CPS 1058 Mulching for Construction Sites (6/2003)
- WDNR CPS 1059 Seeding for Construction Site Erosion Control (11/2003)
- WDNR CPS 1060 Storm Drain Inlet Protection for Construction Sites (6/2016)
- WDNR CPS 1061 Dewatering Practices for Sediment Control (4/2020)
- WDNR CPS 1062 Ditch Check (3/2018)
- WDNR CPS 1067 Temporary Grading Practices for Erosion Control (3/2004)
- WDNR CPS 1068 Dust Control (11/2017)

CHAPTER 6 – AUTHORITY

To the best of my professional knowledge, judgement, and belief, this design meets applicable standards as listen in Chapter 5 of this report.

All of which is respectfully submitted, MSA Professional Services

Juin Cirdun

Jenise Anderson Wisconsin P.E. No. 47342-6 (Expiration 07/31/2024)

APPENDIX A

Construction Plans

2022 EQIP FSA RUNOFF COLLECTION AND WASTE STORAGE FACILITY BROOKS FARMS DAIRY, LLC

WAUPACA COUNTY, WI





LOCATION MAP

OWNER RON BROOKS N1757 COUNTY ROAD A WAUPACA, WI 54981 PHONE: (920) 636-8991

ENGINEEF MSA PROFESSIONAL SERVICES, INC. JENISE ANDERSON, PE OFFICE: (608) 355-8885 CELL: (701) 370-9821

WAUPACA COUNTY LAND AND WATER CONSERVATION DEPARTMENT BRIAN HAASE 811 HARDING ST, WAUPACA, WI 54981 PHONE: (715) 258-6482

SHEET INDEX G - GENERAL SHEETS

G000	TITLE SHEET
G001	EXISTING OVERVIEW
~~ ~~ ~	
CS - CIVIL S	
CS101	PROPOSED OVERVIEW
CS102	PROPOSED WASTE STORAGE PLAN
CS103	
CS104	SAND SEPARATION OVERVIEW
CS301	WSF PROFILE NORTH-SOUTH
CS302	WSF PROFILE WEST-EAST
CS303	FSA WASTE TRANSFER PROFILES
CS304	FLUSH FLUME PROFILES
CS305-306	SAND SEPARATION PROFILES
CS307	ROSSGROUP LINE 1 PROFILE
CS308	ROSSGROUP LINES 2-3,7-8 PROFILES
CS309	ROSSGROUP LINES 10,12,15,18,20 PROFILES
CS310	ROSSGROUP LINES 4-6,9,11,19,21,25,30 PROFILES
CS311	ROSSGROUP LINES 14,17,22,24,27,29 PROFILES
CS312	ROSSGROUP LINES 23,28,40 PROFILES
CS313	ROSSGROUP LINES 26,31,32,34 PROFILES
CS314	ROSSGROUP LINE 35 PROFILE
CS315	ROSSGROUP LINES 13, 16, 36-39 PROFILES
CS316	ROSSGROUP LINE 42 PROFILE
CS317	ROSSGROUP LINES 43-45 PROFILES
CS318	STACKING AREA PROFILES
CS319	ROSSGROUP LINES 41,47,51,52 PROFILES
CS320	ROSSGROUP LINES 48-50 PROFILES
CS501	PIPING DETAILS
CS502	FSA DETAILS
CS503-504	WSF DETAILS
CS505-507	TK-7005 SWECO FEED TANK DETAILS
CS508-511	MANURE TRANSFER DETAILS
CS512	W25000 PRECAST TANK
CS513	W20000 PRECAST TANK
CS514	SHAFT CONNECTOR DETAIL
CS515-518	DETAILS - PENETRATION
CS519	FLUSH TANK - WALL DETAIL
CS520-522	FLUSH TANK DETAILS
S - STRUCI	FURAL
S101	STRUCTURAL GENERAL NOTES & DESIGN STRESSES
S102	STRUCTURAL CONSTRUCTION NOTES
S103	STRUCTURAL SPECIFICATION SHEET
S104	STRUCTURAL SPECIFICATION SHEET

LEGEND

AL SHEETS	w	EXISTING WATER MAIN
TITLE SHEET	—— ⊶ @	EXISTING WATER MAIN. VALVE & HYDRANT
EXISTING OVERVIEW	0	EXISTING WATER SERVICE & CURB STOP
	e	PROPOSED WATER MAIN, VALVE, & HYDRANT
		PROPOSED WATER SERVICE & CURB STOP
		EXISTING SANTARY SEWER & MANHOLE
SAND SEPARATION OVERVIEW		PROPOSED SANITARY SEWER & MANHOLE
WSE PROFILE NORTH-SOUTH		EXISTING FORCEMAIN
WSE PROFILE WEST-EAST	ss	EXISTING STORM SEWER & INLET
FSA WASTE TRANSFER PROFILES		PROPOSED STORM SEWER & INLET
FLUSH FLUME PROFILES	—o —	PROPOSED STORM SEWER & MANHOLE
SAND SEPARATION PROFILES	ε	BURIED ELECTRIC
ROSSGROUP LINE 1 PROFILE	A	
ROSSGROUP LINES 2-3,7-8 PROFILES	о <u>и</u>	
ROSSGROUP LINES 10,12,15,18,20 PROFILES	TV	BURIED CABLE TELEVISION
ROSSGROUP LINES 4-6,9,11,19,21,25,30 PROFILES	T	BURIED TELEPHONE
ROSSGROUP LINES 14,17,22,24,27,29 PROFILES	F0	BURIED FIBER OPTICS
ROSSGROUP LINES 23,28,40 PROFILES	——он——	OVERHEAD UTILITY
ROSSGROUP LINES 26,31,32,34 PROFILES		RAILROAD TRACKS
ROSSGROUP LINE 35 PROFILE		EXISTING CURB & GUTTER
ROSSGROUP LINES 13, 16, 36-39 PROFILES		
ROSSGROUP LINE 42 PROFILE		
ROSSGROUP LINES 43-45 PROFILES		
STACKING AREA PROFILES		PROPOSED SIDEWALK
ROSSGROUP LINES 41,47,51,52 PROFILES	CP	EXISTING CULVERT PIPE
RUSSGRUUP LINES 48-50 PROFILES		PROPOSED CULVERT PIPE
	_ xxx	FENCE LINE
WSE DETAILS		DRAINAGE ARROW
TK-7005 SWECO FEED TANK DETAILS		SILT FENCE
MANURE TRANSFER DETAILS		RIGHT-OF-WAY
W25000 PRECAST TANK		BASELINE
W20000 PRECAST TANK		
SHAFT CONNECTOR DETAIL		PROPERTY LINE
DETAILS - PENETRATION	(Y.Y.Y.Y.Y.Y.Y.) .	TREE LINE
FLUSH TANK - WALL DETAIL	•	BENCHMARK
FLUSH TANK DETAILS	•	IRON PIPE
	•	IRON ROD
	▲	CONTROL POINT
	- o >	UTILITY POLE & GUY
STRUCTURAL GENERAL NOTES & DESIGN STRESSES	⊕ ¹	SOIL BORING
STRUCTURAL SPECIFICATION SHEET	₩ 000.00	
STRUCTURAL SPECIFICATION SHEET	Ä	
WASTE STORAGE TANK FOUNDATION PLAN	×	PEDESTAL
WASTE STORAGE TANK SECTIONS	P	STREET SIGN
WASTE STORAGE TANK ELEVATIONS	Ŷ	MAILBOX
WASTE STORAGE TANK STRUCTURAL DETAILS	6	FLAGPOLE
	ස	TREE - DECIDUOUS
		TREE - CONIFEROUS
	~~~	TREE TO BE REMOVED
	XA	

NO. DATE REVISION BY   PROJECT DATE: DRAWN BY: Init . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . . .	ENGINEERING   ARCHITECTURE   SURVEYING FUNDING   PLANNING   ENVIRONMENTAL 1230 South Boulevard, Baraboo WI 53913 (608) 35-2771 www.msa-ps.com 0 MSA Professional Services, Inc. 8 Control Con
-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

S201

S301

S302

S303



T.	CONTRO	OL POINT TABL	E		CP 503
CP	NORTHING	EASTING	ELEV		
1	322700.1940	546663.3360	834.8130		CP 504
2	322302.3310	545525.7860	827.7930		
3	321441.6990	545530.9930	830.9800		PARLOR RECEPTION TANK
4	321812.5390	546664.0400	831.6410	CP 506	
503	322700.9630	546429.6830	835.0490	FREES	
504	322632.7810	546222.4370	832.7880	RECEPTION	
505	322432.3930	546634.6760	835.6750		
506	322563.5980	545537.9340	831.8690		
507	322346.7030	546386.3330	832.7150	FREESTALL	
508	322307.7870	546160.5560	835.3760		
509	322246.2250	546436.2110	832.4480		
510	322136.0000	546193.2800	834.4920		CP 507
511	322182.0120	546655.5870	833.9530		CP 508
512	321924.2100	546493.0698	831.3510		
513	321966.8250	546247.2060	831.6510		- A pp
					HANGARS
				8304	HEIFER BARN
					SELOND BACKOP WELL - UN280 —
				WETLAND EXTENT	CALF
			- J 'Shi E	€ 2022-1 ₩832.21	7(TP) CP 510
			- (3)/		
$\langle \rangle$				$\leq \langle 3 \rangle$	
		851		$\mathcal{E}^{2}$	25' SETBACK FROM
$\rangle$		A guin		3 J / #	
	75' SETBACK FROM			31 11 11	BIG PIT CP 513
		ASSU	MED 25' SETBACK		
		FROM DELIN	WETLAND EATION TO TAKE		
- ~ -		PLACE	SPRING 2023 —		FEED STORAGE
		830		have stated	× 2022.3 (TP)
				A A A A A A A A A A A A A A A A A A A	€ 2022 (IT) 10
/		+ 511	▲ ST-6		825 830 ²⁶ \$17.18
(F)		€ 832.34		Kan	× × × × × × ×
,			A 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	ST-10	
					Oli-12 Sole borning, TTP.
		← SL2	A 2022-5 (TP)		
		<b>•</b> 836.45	♥ 833.77	Barri	WETLAND INDICATOR
				€-T2	EXTENT PER SWDV
					ST-5 829.00
, /			••••		€ ST-14
		⁸⁴⁰ ⊕ ST-3 839.86		€ 2022-16 (IP) 829.15	● ST-15
		G F	3' SETBACK FROM		€ ⁵¹⁻¹⁶
1				/	
					INTERSECTION VISION TRIANGL
					CL TO CL 150' BACK ON CE
					200' BACK ON CT
1				- Alton of the	
	NO. DA	TE	REVISION	BY	
PROJECT DATE: .	DRAWN BY: Init . DESIGNED BY: Init .		· · ·		2022 EQIP WASTE STORAGE FACILITY
PLOT DATE: 2/24/2023 11:1	CHECKED BY: Init	ments/21752001 G001 Existing Overview.dwg		(608) 356 UT WWL MSA PS COM UKA Professional Service, Inc.	WAUPACA COUNTY, WI









		40
EETBACK (TYP.)		
Т	SOIL BORING, TYP. 2022-10 (TP) 830.21	
PROPOSED	FEED STORAGE PLAN	PROJECT NO. 21752002 SHEET CS103





#### A-A WSF NORTH SOUTH PROFILE

		1	NO.	DATE	REVISION	BY	_		
PROJECT DATE: .	DRAWN BY:	Init						FUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WASTE STO
	DESIGNED BY:	Init			· _			1230 South Boulevard, Baraboo WI 53913	BROOKS FARMS D
	CHECKED BY:	Init			· · · · · · · · · · · · · · · · · · ·			(608) 356-2771 www.msa-ps.com	WALIPACA COUL
PLOT DATE: 2/24/2023 11:14 PM G:\21\2	1752\21752001\CAI	DD\Constru	uction	Documents ¹	21752001 WSE PROFILES dwg			C MSA Professional Services, Inc.	

RAGE FACILITY AIRY, LLC NTY, WI

	PROJECT NO. 21752002
WSF FROFILE - NORTH SOUTH	SHEET CS301



**B-B WSF WEST EAST PROFILE** 

Station

		1	10.	DATE	REVISION	BY	
PROJECT DATE: .	DRAWN BY:	nit					
	DESIGNED BY:	nit			· _		1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	nit	•				(608) 356-2771 www.msa-ps.com
DLOT DATE: 2/24/2022 11:14 DM C:12	017E2017E20010CADD	Constru	otion	Decumentel	217E2001 WEE DROEILES dura		© MSA Professional Services. Inc.







		NO.	DATE	REVISION		_		
PROJECT DATE: .	DRAWN BY: Init						FUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WASTE STORAGE FACILITY
	DESIGNED BY: Init				- (0	$\infty$ MSA	1230 South Boulevard, Baraboo WI 53913	BROOKS FARMS DAIRY, LLC
	CHECKED BY: Init	•		· · · · · · · · · · · · · · · · · · ·	- 24	SIIOA	(608) 356-2771 www.msa-ps.com	WALIPACA COUNTY WI
PLOT DATE: 2/24/2023 11:16 PM, G:\21	\21752\21752001\CADD\Con	truction	Documents\	21752001 - CS304 Waste Transfer Profiles.dwg			© MSA Professional Services, Inc.	

FLUSH FLUME PROFILES



			NO.	DATE	REVISION		_
PROJECT DATE: .	DRAWN BY:	Init					
	DESIGNED BY:	Init				•	(0) MSA
	CHECKED BY:	Init				•	
PLOT DATE: 2/24/2023 11:16 PM, G:\21\2	1752\21752001\CADE	)\Cons	truction	Documents\	21752001 - CS304 Waste Transfer Profiles.dwg		



Station

1 - CS304 Waste Transfer Profiles dw

NO.

Init

DRAWN BY:

LOT DATE: 2/24/2023 11:16 PM, G:\21\21752\21752001\CADD\Cc

DESIGNED BY: Init CHECKED BY: Init

OUECT DATE

ALL HDPE GRAVITY PIPE JOINTS SHALL MEET ASTM D3212 JOINT PERFORMANCE SPECS.

•	<b>MSA</b>	ENGINEERING   ARCHITECTURE   SURVEYING FUNDING   PLANNING   ENVIRONMENTAL 1230 South Boulevard, Baraboo WI 53913 (608) 356-2771 www.msa-ps.com	20
		© MSA Professional Services, Inc.	





Station

			NO.	DATE	REVISION		_		
PROJECT DATE: .	DRAWN BY:	Init							FUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY:	Init			· _		່ໄແກງ	MSA	1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init			. "				(608) 356-2771 www.msa-ps.com
LOT DATE: 2/24/2023 11:16 PM, G\21/21752/21752001\CADD\Construction Documents\21752001 - CS304 Waste Transfer Profiles.dwg									© MSA Professional Services, Inc.

	21752002
Resserver line trachel	SHEET CS307



			NO.	DATE	REVISION	BY	
PROJECT DATE: .	DRAWN BY:	Init					FUNDING   PLANNING   ENVIRONMEN
	DESIGNED BY:	Init			· _		1230 South Boulevard, Baraboo WI 539
	CHECKED BY:	Init					(608) 356-2771 www.msa-ps.com
PLOT DATE: 2/24/2023 10:38 PM C:\2:	121752121752001\CA			© MSA Professional Services, Inc.			

WAUPACA COUNTY, WI



			market best states in the states in the
	10		(608) 356-2771 www.msa-ps.com
		MSA	1230 South Boulevard, Baraboo WI 53913
		N40 A	FUNDING   PLANNING   ENVIRONMENTAL
BY	_		ENCINEEDING LADCHITECTURE   SUDVEVING

	DRAWN BY:	Init	•	•	+	
	DESIGNED BY:	Init			÷_	i ((
	CHECKED BY:	Init			· •	24
PM, G:\21\2	1752\21752001\CAD	D\Cons	truction	Documents\	DIGESTER PROFILES.dwg	1




		NO.	DATE	REVISION	BY	_					
PROJECT DATE: .	DRAWN BY: Init							EUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WASTE STORAGE FACILITY		
	DESIGNED BY: Init			· _		((()))	MSA	1230 South Boulevard, Baraboo WI 53913	BROOKS FARMS DAIRY, LLC		
	CHECKED BY: Init					12		(608) 356-2771 www.msa-ps.com	WALIPACA COUNTY WI		
PLOT DATE: 2/24/2023 10:39 PM, G:\21\21752\21752\001\CADD\Construction Documents\CS 310 DIGESTER PROFILES 2.dwg								© MSA Professional Services, Inc.			

IEE 15 C5515	- 518.	TIPATIN
840		
836	CONNECT TO D2 ELEV - 837.58 (6) TANK PENETRATION TO BE WATERTIGHT USING SHAFT LINING	
832	SEE DETAIL SHEET 514. ALSO SEE SHEETS CS515 - 518.	
828	LINE 6 - 346 L.F. 6" PE SDR-17 (ASTM F 714)	
824	DIGESTER 2 SEE PLANET/MPE PLANS	
820		
.F.		
816		
812		
828.3		
3+56.39		

	21752002					
ROSSGROUP LINES 4-6,9,11,19,21,25,30 PROFILES						





			NO.	DATE	REVISION	BY			
OJECT DATE: .	DRAWN BY:	Init							EUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY:	Init					1 ((()))	MSA	1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init							(608) 356-2771 www.msa-ps.com
T DATE: 2/24/2023 10:39 PM G \21/21752\21752\21752\201\CADD\Construction Documents\CS 310 DIGESTER PROFILES 2 dwg									© MSA Professional Services, Inc.





21752002 ROSSGROUP LINES 26,31,32,34 PROFILES CS313

PROJECT NO

- CONNECT TO SOLID SEPARATION EQUIPMENT ELEV. = 832.00

FEED INTO SUCTION END OF BOERGER PL200 (P&ID P-7101) PUMP TO FEED SEPARATOR IN MEZZANINE OF SOLID SEPARATION BUILDING

BOERGER PL 200 PUMP IS LOCATED IN TC#4



	PROJECT NO. 21752002
RUSSGROUP LINE 35 PROFILE	SHEET CS314



BROOKS FARMS DAIRY, LLC	
WAUPACA COUNTY, WI	

颅 MSA

ROJECT DATE

1 OT DATE: 2/24/2023 10:40 PM G:\2

CHECKED BY: Init

DIGESTER PROFILES 4.dwg



CONNECT TO HT #3 ELEV - 832.74 TANK PENETRATION TO BE WATERTIGHT USING SHAFT LINING SEE DETAIL SHEET 514. ALSO SEE SHEETS CS515 - 518

HYDROLYSIS TANK #3 SEE PLANET/MPE PLANS

LINE 38 - 287 L.F. 8" SDR-11 HDPE (ASTM F 714)

	21752002
Resserver lines 13, 10, 30-39 FROMELS	SHEET CS315



			NO.	DATE	REVISION	BY	_		_
PROJECT DATE: .	DRAWN BY:	Init				÷		FUNDING   PLANNING   ENVIRONMENTAL	
	DESIGNED BY:	Init				÷		1230 South Boulevard, Baraboo WI 53913	
	CHECKED BY:	Init			· •			(608) 356-2771 www.msa-ps.com	
PLOT DATE: 2/24/2023 10:41 PM, G:\21\21752\21752\01\CADD\Construction Documents\CS316 DIGESTER PROFILES 5.dwg							1	© MSA Professional Services, Inc.	











Station



			NO	. DATE	REVISION BY	(	_				
F	ROJECT DATE: .	DRAWN BY:	Init .					FUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WASTE STORAGE FACILITY		
Г		DESIGNED BY:	Init .			<b>))</b> T	))MSA	1230 South Boulevard, Baraboo WI 53913	BROOKS FARMS DAIRY, LLC		
		CHECKED BY:	Init .					(608) 356-2771 www.msa-ps.com	WALIPACA COUNTY WI		
F	LOT DATE: 2/24/2023 10:42 PM, G:\21\2	1752\21752001\CAD	D\Constructi	on Document	s\21752001 - CS319 Digester Profiles 6.dwg			© MSA Professional Services, Inc.			

PROJECT NO. 21752002



CS502. MANHOLE MUST MEET ASTM C-478, BASE SECTION SHALL HAVE RISER WALL AND BASE SLAB MONOLITHICALLY CAST



Station



Station

		N	10.	DATE	REVISION			_	ENCINEERING LARCHITECTURE   SURVEYING
PROJECT DATE: .	DRAWN BY:	Init					7		FUNDING   PLANNING   FNVIRONMENTAL
	DESIGNED BY:	Init			· _		T ((	O) MSA	1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init				-	] 🗸	SIICA	(608) 356-2771 www.msa-ps.com
LOT DATE: 2/24/2023 10:42 PM, G:\211/21752\21752001\CADD\Construction Documents\21752001 - CS319 Digester Profiles 6.dwg									© MSA Professional Services, Inc.

2022 EQIP WASTE STORAGE FACILITY BROOKS FARMS DAIRY, LLC WAUPACA COUNTY, WI



PROJECT NO

ROSSGROUP LINES 48-50 PROFILES







- PRIOR TO PLACING CONCRETE OVER THE WATERSTOP. THE REQUIRED CURING TIME WILL BE TEMPERATURE DEPENDENT
- ON THE AMOUNT OF CONCRETE COVER PROVIDED.
- REMOVED AND REPLACED FOLLOWING ALL OF THE INITIAL INSTALLATION REQUIREMENTS.



- DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION
- ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF AASHTO DESIGNATION M 199. PRECAST REINFORCED BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH. WHICH
- UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE
- OTHERWISE SHOWN OR NOTED.





2022 EQIP WASTE STORAGE FACILITY
BROOKS FARMS DAIRY, LLC
WAUPACA COUNTY, WI

ENGINEERING | ARCHITECTURE | SURVEYING

FUNDING | PLANNING | ENVIRONMENTAL

1230 South Boulevard, Baraboo WI 53913

(608) 356-2771 www.msa-ps.com

颅 MSA

 R

NO. DATE

DRAWN BY:

DESIGNED BY: Init

CHECKED BY: Init

Init

ROJECT DATE

PLOT DATE: 2/24/2023 10:43 PM G:\21

	PROJECT NO. 21752002
WSF DETAILS	SHEET CS503

DANGER	DROWNING HAZARD!
LIQUID MANURE STORAGE	SURFACE MAY BREAK THROUGH KEEP OFF SURFACE
PELIGRO	PELIGRO
ALMACENAJE DE ESTIÉRCOL LÍQUIDO	PELIGRO DE AHOGARSE!
THIS IS ONLY AN EXAMPLE OF THE TYPE OF SIGN THAT MUST BE POSTED AROUND THE FACILITY. OTHER COMMERCIALLY AVAILABLE SIGNS MAY BE USED.	SUPERFICIE SE PUEDE QUEBRAR MANTENGASE FUERA THESE ARE ONLY EXAMPLES OF THE
United States Department of Agriculture Natural Resources Conservation Service	AROUND THE FACILITY. OTHER COMM
NO.         DATE         REVISION         BY           OLECT DATE:         DRAWN BY:         int         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .         .	2022 EQIP WASTE STORAGE FACILITY BROOKS FARMS DAIRY, LLC WAUPACA COUNTY, WI

BROOKS FARMS E
WAUPACA COU





			NO.	DATE	REVISION	BY			
PROJECT DATE: .	DRAWN BY:	Init				÷			FUNDING   F
	DESIGNED BY:	Init			· · · · ·	÷	່ແກ	MSA	1230 South
	CHECKED BY:	Init							(608) 35
PLOT DATE: 2/24/2023 10:43 PM G:\21\2	1752\21752001\CAF	DD\Con	struction	Documents\	21752001 Details dwg				01

WAUPACA COUNTY, WI

2. HORIZ (DESIGN	WALL STEEL WALL HEIGHT 7 FT. or less 8 FT. 8 FT. 10 FT. 10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CARTE	WALL THICKNESS 8" 12" 8" 10" 12" 12"	NO TRACTO GRADE 40 #4 @ 12" #4 @ 12" #5 @ 9" #5 @ 9" #5 @ 9" #5 @ 9"	LOA R ADJACENT GRADE 60 #4 © 18" #4 © 18" #5 © 12" #4 © 12" #4 © 15" #5 @ 12"	DING TRACTOR GRADE 40 #4 © 10" #4 © 12" #6 © 9" #5 © 9" #4 © 7" #6 © 9" #6 © 9"	ADJACENT GRADE 60 #4 @ 16" #5 @ 18" #4 @ 18" #6 @ 12" #5 @ 12"
2. HORIZ (DESIGN	WALL HEIGHT           7         FT. or less           8         FT.           10         FT.           12         FT.           20NTAL         WALL           STEFE         FO. TO. ACI. 318	WALL THICKNESS 8" 12" 12" 10" 12" 12"	NO TRACIQ GRADE 40 #4 @ 12" #4 @ 12" #5 @ 9" #5 @ 12" #4 @ 9" #5 @ 9"	R         ADJACENT           GRADE         60           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #4         18"           #5         12"           #4         15"           #5         12"	TRACTOR           GRADE 40           #4 @ 10"           #4 @ 7"           #4 @ 12"           #6 @ 9"           #5 @ 9"           #4 @ 7"	ADJACENT GRADE 60 #4 @ 16" #5 @ 18" #4 @ 18" #6 @ 12" #5 @ 12"
2. HORIZ	MALL           HEIGHT           7 FT. or less           8 FT.           10 FT.           10 FT.           10 FT.           12 FT.           20NTAL WALL STEE           ED TO ACI 318 CRIFE	THICKNESS 8" 8" 12" 12" 10" 12" 10" 12"	GRADE 40 #4 @ 12" #4 @ 12" #4 @ 18" #5 @ 9" #5 @ 12" #4 @ 9" #5 @ 9"	GRADE 60 #4 @ 18" #4 @ 18" #5 @ 12" #4 @ 12" #4 @ 12" #4 @ 15" _#5 @ 12"	GRADE 40 #4 @ 10" #4 @ 7" #4 @ 12" #6 @ 9" #5 @ 9" #4 @ 7" #6 @ 9"	GRADE 60 #4 @ 16" #5 @ 18" #4 @ 18" #6 @ 12" #5 @ 12"
2. HORIZ (DESIGN	7 FT. or less 8 FT. 10 FT. 10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CRITE	8" 12" 8" 10" 12" 12"	#4 @ 12" #4 @ 12" #4 @ 18" #5 @ 9" #5 @ 12" #4 @ 9" #5 @ 9"	#4 @ 18" #4 @ 18" #5 @ 12" #4 @ 12" #4 @ 12" #4 @ 15" _#5 @ 12"	#4 @ 10" #4 @ 7" #4 @ 12" #6 @ 9" #5 @ 9" #4 @ 7" #6 @ 9"	#4 @ 16" #5 @ 18" #4 @ 18" #6 @ 12" #5 @ 12"
2. HORIZ (DESIGN	8 FT. 8 FT. 10 FT. 10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CARTE	8" 12" 8" 10" 12" 12"	#4 ☺ 12" #4 ☺ 18" #5 ☺ 9" #5 ☺ 12" #4 ☺ 9" #5 ☺ 9"	#4 @ 18" #4 @ 18" #5 @ 12" #4 @ 12" #4 @ 15" _#5 @ 12"	#4 © 7" #4 © 12" #6 © 9" #5 © 9" #4 © 7" #6 © 9"	#5 @ 18" #4 @ 18" #6 @ 12" #5 @ 12"
P. HORIJ (DESIGN	8 FT. 10 FT. 10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CRITEI	12" 8" 10" 12" 12"	#4 @ 18" #5 @ 9" #5 @ 12" #4 @ 9" #5 @ 9"	#4 © 18" #5 © 12" #4 © 12" #4 © 15" #5 © 12"	#4 @ 12" #6 @ 9" #5 @ 9" #4 @ 7" #6 @ 9"	#4 @ 18" #6 @ 12" #5 @ 12"
. HORIJ (DESIGN	10 FT. 10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CRITEI	8" 10" 12" 12"	#5 @ 9" #5 @ 12" #4 @ 9" #5 @ 9"	#5 @ 12" #4 @ 12" #4 @ 15" _#5 @ 12"	#6 @ 9" #5 @ 9" #4 @ 7" #6 @ 9"	#6 @ 12" #5 @ 12"
. HORI (DESIGN	10 FT. 10 FT. 12 FT. 20NTAL WALL STEE ED TO ACI 318 CRITEI	10* 12" 12"	#5 @ 12" #4 @ 9" #5 @ 9"	#4 @ 12" #4 @ 15" #5 @ 12"	#5 @ 9" #4 @ 7" #6 @ 9"	#5 @ 12"
. HORI (DESIGN	10 FT. 12 FT. ZONTAL WALL STEE ED TO ACI 318 CRITEI	12" 12"	#4 @ 9" #5 @ 9"	#4 @ 15" #5 @ 12"	#4 @ 7" #6 @ 9"	
2. HORIJ (DESIGN	20NTAL WALL STEE	12"	<b>#5 @ 9</b> ″	<i>#</i> 5 © 12"-	#6 @ 9"	#4 @ 10"
2. HORIZ (DESIGN	ZONTAL WALL STEE	a			10 0 0	#6 @ 15"
	LOADING	- 1. LIVESTO	CK (125 psf) TEER LOADER (1)	50 pst	- 1	
		J. INACION	(Z=5000EB. E			î
F			LOADING	(GRADE 40)		
<u>_</u>	WIDTH	1	2	#A @ A"	J 	
	6 FI.	#4 @ 12	#4 @ 10	#5 @ 4"	#5000 #606"	
F	10 57	#4 @ 7"	#4 @ 7"	#6 @ 4"	#7.@ 5"	
H	12 FT	#6 @ 11"	#6 @ 10"	#7 @ 4" 0	#8@4"	
L.	12 104 1	10 0 11			1000	
	<u> </u>		LOADING	(CRADE 60)		1
15	WIDTH	1	LUADING	GRADE DU)	3	1
H	e et	#A @ 12"	#A @ 12"	#3 @ 4" 0	v #4.@ 6"	1
-	8 57	#4 @ 12"	#4 @ 12"	#4 @ 4"	v #5 @ 6"	
-	10 FT	#4 @ 11"	#4 @ 10"	#5 @ 4"	#6 @ 6"	
F	12 1	#5 @ 12"	#5 @ 11"	#5 @ 3" c	r #6 @ 4"	1
		10012	1 11	1		1. Contraction of the second
0.72						

					/	
				/		
		WALL	HEIGHT - 8	FI.		
THICKNESS	0		SPAN ALONG	TUP UP W	ALL	ET
THORNEOU	CRADE 40	GRADE 60	CRADE 40	GRADE 60	GRADE 40	GRADE 60
	3 - #6	3 - #5	3 #7	4 - 45	4 - #8	4 - #7
8"	4 - #5	2 - #6	4 - #6	3 - #6		
	3 - #5	3 - #4	3 - #6	4 - 14	3 - #7	4 - #5
10	4 - #4	2 - #5	4 - #5	3 - 15	4 - #6	3 - #6
12"	3 - #4	2 - #4	3 - #5	.2 - <b>f</b> 5	3 - #6	2 - #6
	$\leq$	<u></u>				<b>`</b>
WALL		WALL	HEIGHT - TU	TOP OF W	MI	
THICKNESS		FT	SPAN ALONG	FT FT	18	FT
1110111200	GRADE 40	GRADE 60	GRADE 40	GRADE 60	GRADE 40	GRADE 60
La.	4 - #6	4 - #5	4 - #8	4 - #6	THICKEN	THICKEN
87		3 - #6	X		WALL.	WALL
10"	3 - #6	3 - #5	3 - #7	4 - #5	4 - ∦8	4 - #6
B 10	4 - #5	2 - #6	4 - #6	3 - #6		l?
4.00	2 - #6	2 #5	2 - #8	2 - #6	3 - #8	3 - #6
12		1				
12	3 - #5	Wall	3 - #6	ET.	A #7	\]
WALL	3 - #5	IWALL	3 - #6 HEIGHT' - '12 SPAN ALONG	FT.	4 #7	
WALL	3 - #5	WALL	3 - #6 HEIGHT - 12 SPAN ALONG - 10	FT TOP OF W.	ALL 12	
WALL THICKNESS	3 - #5 8 GRADE 40	WALL FT. GRADE 60	3 - #6 HEIGHT - 12 SPAN ALONG - 10 GRADE '40	FT. TOP OF W FT. GRADE 60	ALL 12 GRADE 40	2 FT. GRADE 60
WALL THICKNESS	3 - #5 8 GRADE 40 4 - #7	WALL FT.   GRADE 60   4   #6	3 - #6 HEIGHT - 12 SPAN ALONG 10 GRADE '40 'THICKEN WALL	FT. TOP OF W FT. GRADE 60 THICKEN WALL	ALL D. GRADE 40 I. THICKEN WALL	FT. GRADE 60 THICKEN WALL
WALL THICKNESS	3 - #5 B GRADE 40 4 - #7 -3 - #7	WALL FT. GRADE 60 4 - #6 4 - #5	BADE 40	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6	ALL D GRADE 40 I THICKEN WALL THICKEN	2 FT. GRADE 60 THICKEN WALL THICKEN
WALL THICKNESS	3 - #5 8 GRADE 40 4 - #7 3 - #7 4 - #6	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6	BADE 40	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6	ALL ALL GRADE 40 THICKEN WALL THICKEN WALL	2 FT. GRADE 60 THICKEN WALL THICKEN WALL
WALL THICKNESS 8" 10"	3 - #5 8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7	WALL FT. GRADE 60 4 #6 4 #5 3 #6 2 #6	3 - #6 HEIGHT - 12 SPAN ALONG - 10 GRADE 40 'THICKEN WALL - #8 #8	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL GRADE 40 GRADE 40 THICKEN WALL THICKEN WALL A - #8	2 FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7
WALL THICKNESS 8" 10" 12"	3 - #5 8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 500 51 41 4	WALL FT. GRADE 60 4 - #6 3 - #6 2 - #6	3 - #6 HEIGHT' - 12 SPAN ALONG - 10 GRADE '40 'THICKEN WALL - #8 - 3 - #8	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - ↓6 3 - ↓6	ALL GRADE 40 GRADE KAN WALL THICKEN WALL 4 - #8	2 FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7
WALL THICKNESS 8" 10" 12" STRUCTION NOTE EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS SPAN ALONG T SPACING ALONG ALONG T SPACING ALONG ALONG ALONG ALONG T SPACING ALONG ALON	3 - #5 8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 S FOR SLAT A ALWAYS REQU OOR SLAE ATI OOR SLAE ATI	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 2 - #	ALLS WHEN T ALLS WIEN T ALLS WIEN T ALLS WHEN T ALLS WHEN T ALLS WHEN T ALLS WHEN T ALLS WHEN T ALLS WHEN T ANK WIDTH FO E 12. FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6 WALL. HE BEAM R THE N ALONG THE TS AT	ALL C GRADE 40 1 THICKEN WALL 1 THICKEN WALL 4 - #8	2 FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7
WALL THICKNESS B" 10" 12" STRUCTION NOTE EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS EXTRA STEEL IS SPACING ALONG FI "SPAN ALONG FI SPACING ALONG ENDWALLS, TOP OF WALL" O&M PLAN: "NE ONE TIME FOR WINITED ST Departm	3 - #5 B GRADE 40 4 - #7 3 - #7 3 - #6 2 - #7 3 - #6 S FOR SLAT A ALWAYS REQL OOR SLAB ATT DP OF WALL THE SIDEWALL IK WITH NO B COLUMN ABOVE VER REMOVE N ANY REASON." THES STOR SLAT A ALWAYS REQL OOR SLAB ATT DP OF WALL THE SIDEWALL IK WITH NO B COLUMN ABOVE VER REMOVE N ANY REASON."	WALL FT. GRADE 60 A - #6 A	ALLS WHEN T TOP OF THE REFERS TO T ANK WIDTH FO TANK DESIG	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6 THERE IS WALL. HE BEAM R THE N ALONG THE TS AT	ALL D. GRADE 40 I. THICKEN WALL THICKEN WALL 4 - #8 HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD HEAD H	Dote File WH-7
WALL THICKNESS B" 10" 12" STRUCTION NOTE EXTRA STEEL IS NO BUILDING FI SPACING ALONG ENDWALLS. FOR A SLAT TAI TOP OF WALL" O&M PLAN: "NE ONE TIME FOR WINTE FOR United St Departm Agricultu	3 - #5 B B GRADE 40 4 - #7 3 - #7 3 - #6 2 - #7 3 - #6 S FOR SLAT A ALWAYS REQL OOR SLAB ATT OOR SLAB	WALL FT. GRADE 60 A - #6 A	3 - #6 HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8 3 - #8 LAT TANKS: ALLS WHEN T TOP OF THE REFERS TO T ANK WIDTH FO E 12 FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W FT. GRADE- 60 THICKEN WALL 4 - #6 3 - #6 THERE IS WALL. HE BEAM R THE N ALONG THE TS AT	ALL D GRADE 40 D GRADE 40 I THICKEN WALL THICKEN WALL 4 - #8 Hesigned MSA Trown	Dote File WALL THICKEN WALL THICKEN WALL 4 - #7 Dote 01/0
WALL THICKNESS B" 10" 12" STRUCTION NOTE EXTRA STEEL IS NO BUILDING FI SPACING ALONG ENDWALLS. FOR A SLAT TAI TOP OF WALL" O&M PLAN: "NE ONE TIME FOR WINTE FOR United St Departm Agricultu	3 - #5 B GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 S FOR SLAT A ALWAYS REQU OOR SLAB ATI OOR SLAB ATI OOR SLAB ATI OOR SLAB ATI OP OF WALL THE SIDEWALL IK WITH NO B COLUMN ABOVE VER REMOVE 1 NNY REASON." THE SIDEWALL IK WITH NO B COLUMN ABOVE VER REMOVE 1 NNY REASON."	WALL FT. GRADE 60 A - #6 A - #6 GRADE 60 A - #6 GRADE 60 A - #6 A - #	ALLS WHEN T ALLS	FT. TOP OF W FT. GRADE-GC THICKEN WALL 4 - #6 3 - #6 THERE IS WALL. HE BEAM R THE N ALONG THE TS AT	ALL ALL GRADE 40 GRADE 40 GRADE 40 GRADE 40 HICKEN WALL THICKEN WALL 4 - #8 HE HICKEN WALL 4 - #8	Dote         File           0         THICKEN           WALL         THICKEN           WALL         THICKEN           WALL         THICKEN           WALL         4           4         #7           Dote         03/2

			NO.	DATE	REVISION	BY		
PROJECT DATE: .	DRAWN BY:	Init						FUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY:	Init	•		· _		(0) MSA	1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init				-		(608) 356-2771 www.msa-ps.com
PLOT DATE: 2/24/2023 10:43 PM, G:\21\2	1752\21752001\CAE	DD\Cons	struction	Documents\	21752001 Details.dwg			© MSA Professional Services, Inc.

	PROJECT NO. 21752002
TR-7003 SWECO FEED TANK DETAILS	SHEET CS506

5. HORIZONTAL REINFORCEMENT FOR WALL CORNERS	(A) BARS ON DRAWING WI-745 )
(DESIGNED TO ACI 318 CRITERIA)	

			NO_SUF	RCHARGE					
HICKNE		GRADE 40		GRADE 60					
HEIGHT	8"	10"	12"	8"	10"	12"			
7'	#4 @ 12"	NA	NA	#4 @ 18"	NA	NA			
8'	#4 @ 10"	#4 @ 14"	TS	#4_@_16"	#4 @ 18"	TS			
10'	#5 @ 8"	#5 @ 10"	TS	#5 @ 12"	#4 @ 10"	TS			
12	#6 @ 6"	#5 @ 6"	#5 @ 8"	#5 @ 6'	#5 @ 10"	#5 @ 12"			

			WITH SL	IRCHARGE		
HICKNE		GRADE 40			GRADE 60	
HEIGHT	8"	10"	12"	8*	10"	12"
7'	#4 @ 10"	NA	NA	#4 @ 12"	NA	NA
8'	#4 @ 6"	#4 @ 10"	TS	#4 @ 10"	#4 @ 15"	TS
10'	#5 @ 6"	#5 @ 8"	#5 @ 10"	#4 @ 6'	#4 @ 8"	#4 @ 10"
12'	NA	NA	#5 @ 6"	NA	NA	#5 @ 9°

TS - NO ADDITIONAL STEEL NEEDED

NA - NOT APPLICABLE COMBINATION OF THICKNESS AND HEIGHT

6. TYPICAL PRECAST LID THICKNESSES

SLATS FOR LIVESTOCK - 6" SLATS FOR EQUIPMENT - 9 1/2" DRIVE THROUGH PANEL - 9 1/2"

[*ANY PRECAST COMPONENTS SHALL BE DESIGNED FOR THE MAXIMUN LOADING CONDITIONS ANTICIPATED

7. JANK BOTTOM SLAB REINFORCEMENT (DESIGNED TO ACI 318 CRITERIA)

TANK BOTTOM SLAB SHALL HAVE REINFORCEMENT EQUAL TO OR GREATER THAN THE FOLLOWING

	REBAR SIZE (GR 60) AND SPACING						
SLAB THICKNESS	SLAB LENGTH*						
(INCHES)	<100'	<150'	<175				
	#4 @ 10"	<b>#</b> 4 @ 7"	<b>#4 @ 6</b> [™]				
10	<b>#5 @ 16</b> "	#5 @ 11"	#5 @ 9"				
1	#4 @ 8"	#4 @ 5"	#4 @ 5"				
12	#5 @ 13"	#5 @ 9"	#5 @ 7.5"				

REINFORCING STEE THE "SHO (TANKS 12' C	L FOR TANK SLABS IN RT" DIRECTION R LESS IN WIDTH)
SLAB THICKNESS (INCHES)	REBAR SIZE (GR 60) AND SPACING
10	#4 @ 10"
10	#5 @ 16"
10	#4 @ B"
12	#5 @ 13"

*SLAB LENGTH OR DISTANCE BETWEEN WATERSTOP JOINTS IN SLAB.

USDA United States	RECEPTION TANK DESIGN	DesignedMSA	File Nome WI-741C
Agriculture	BROOKS FARMS	Drawn	Date 03/2019
Natural Resources Conservation Service	WAUPACA	Approved	Sheet of

		1					LOA	DING					
			NO TR	RACTO	R ADJACENT	_		[	TRAC	TOR	ADJACENT		
		GRA	DE 40	)	GRADE 60		GRADE 40			GRADE 60		200	
WALL	WALL			1	10010 010	- P		1000	D		LIDOK BAD		
(FEET)	(INCHES)	SIZE	R (in)	S (in)	SIZE	R (in)	(in)	SIZE	(in)	5 (in)	SIZE	(in)	ir
7 OR LESS	8	4	19	8	4	22	8	4	19	8	4	22	8
8	×8	4	19	8	4	22	8	4	19	8	4	22	8
8	12	4	21	8	4	24	8	4	21	8	4	24	8
10	c6 <b>8</b> 2	4	19	8	4	22	8	4	19	8	4	24	8
10	10	4	19	8	4	22	8	4	19	8	4	22	8
10	12	4	21	8	4	24	8	4	21	8	4	24	8
12	12	4	21	8	4	24	8	5	22	10	5	28	1
		F	2-		Ĩ								
		F	2		D D PE 2	2)	Bł	∕−S \R					
		F	- +	TY	PE 2	1	Bł	∕−S AR					
SDA	United Stat	F		TY	PE 2	1	Bł	S R Designed	MS	٨	Dote	File h	
SDA .	United Stat	es t of	REC	TY			B	S AR Designed Drawn	- MS	A	Dote	File N Wi⊣72	lame \$1D
SDA	United Stat Departmeni Agriculture	es t of	REC	EPTIK	DN TANK D	1 ESIG	Bł	Designed Drown Checked	- MSJ	A	Dete	File N Wi–72 Dote 03/20	lame +1D

			NO.	DATE	REVISION B	BY	_	
PROJECT DATE: .	DRAWN BY:	Init	•					FUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY:	Init	•		·			1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init	•		· •		SIICA	(608) 356-2771 www.msa-ps.com
PLOT DATE: 2/24/2023 10:43 PM G:\21\2	1752\21752001\CA		struction			© MSA Professional Services, Inc.		



	21752002
TR-7003 SWEED FEED TANK DETAILS	SHEET CS507





			NO.	DATE	REVISION	BY			
PROJECT DATE: .	DRAWN BY:	Init						FUNDING   PLANNING   ENVIRONMENTAL	1
	DESIGNED BY:	Init					(0) MSA	1230 South Boulevard, Baraboo WI 53913	1
	CHECKED BY: Init .				1 SINGA	(608) 356-2771 www.msa-ps.com	1		
PLOT DATE: 2/24/2023 10:43 PM, G:\21\2	21752\21752001\CA	DD\Con:	struction	Documents		© MSA Professional Services, Inc.	1		





GENERAL NOTES:

- 1. DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO ASTM D2321.
- 2. CLASS 1A EMBEDMENT MATERIAL SHALL BE CLEAN, OPEN GRADED CRUSHED STONE, ROCK OR GRAVEL.
- 3. NO PARTICLES LARGER THAN 1 INCH SHALL BE USED IN THE PIPE EMBEDMENT.
- CLASS 1 MATERIAL IS SUITABLE AS FOUNDATION AND FOR REPLACING OVER-EXCAVATED AND UNSTABLE TRENCH BOTTOM. INSTALL AND COMPACT IN 6-INCH MAXIMUM LAYERS. 4.
- 5. INSTALL BEDDING IN 6-INCH MAXIMUM LAYERS. LEVEL FINAL GRADE BY HAND. MINIMUM DEPTH 4 INCH (6 INCH IN ROCK CUTS).
- INSTALL AND COMPACT HAUNCHING IN 6-INCH MAXIMUM LAYERS. WORK IN AROUND PIPE BY HAND 6. TO PROVIDE UNIFORM SUPPORT.
- 7. INSTALL AND COMPACT INITIAL BACKFILL TO A MINIMUM OF 6 INCH ABOVE PIPE CROWN.
- 8. EMBEDMENT COMPACTION:

CLASS 1A: PLACE AND WORK BY HAND TO INSURE ALL EXCAVATED VOIDS AND HAUNCH AREAS ARE FILLED. FOR HIGH DENSITIES USE VIBRATORY COMPACTORS.

CLASS I - FLEXIBLE PIPE EMBEDMENT DETAIL FOR DRAIN TILE A CS510 UNDER THE WASTE STORAGE FACILITY

GENERAL NOTES:

- 4. CLASS III MATERIAL IS SUITABLE AS FOUNDATION AND FOR REPLACING OVER-EXCAVATED TRENCH BOTTOM. DO NOT USE IN THICKNESS GREATER THAN 12 INCH TOTAL. INSTALL AND COMPACT IN 6-INCH MAXIMUM LAYERS.
- MINIMUM DEPTH 4 INCHES (6 INCH IN ROCK CUTS).
- 6. INSTALL AND COMPACT HAUNCHING IN 6-INCH MAXIMUM LAYERS. WORK IN AROUND PIPE BY HAND TO PROVIDE UNIFORM SUPPORT.
- 7. INSTALL AND COMPACT INITIAL BACKFILL TO A MINIMUM OF 6 INCHES ABOVE PIPE CROWN. 8. EMBEDMENT COMPACTION:
- MINIMUM DENSITY 90% STANDARD PROCTOR. USE HAND TAMPERS OR VIBRATORY COMPACTORS. MAINTAIN MOISTURE CONTENT NEAR OPTIMUM TO MINIMIZE COMPACTIVE EFFORT.
- B CLASS III FLEXIBLE PIPE EMBEDMENT DETAIL FOR TRANSFER PIPE CS510 24" FLUME TRANSFER PIPE

			NO.	DATE	REVISION BY			
DATE: .	DRAWN BY:	Init					FUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WA
	DESIGNED BY:	Init	•		· _ · ·	1(0) MSA	1230 South Boulevard, Baraboo WI 53913	BROOK
	CHECKED BY:	Init			· · · · · · · · · · · · · · · · · · ·		(608) 356-2771 www.msa-ps.com	WAU
- 2/24/2022 10:42 DM C:\21\2	1752021752001004		truction	Dooumonto	MANURE TRANSFER DETAILS durg		© MSA Professional Services. Inc.	11/10

1. DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO ASTM D2321. 2. CLASS III EMBEDMENT MATERIAL SHALL BE COURSE-GRAINED SOILS WITH FINES. NO PARTICLES LARGER THAN 1 INCH SHALL BE USED IN THE PIPE EMBEDMENT.

3. DO NOT USE WHERE WATER CONDITIONS IN TRENCH MAY CAUSE INSTABILITY.

5. INSTALL AND COMPACT BEDDING IN 6-INCH MAXIMUM LAYERS. LEVEL FINAL GRADE BY HAND.

	21752002
MANURE TRANSFER DETAILS	SHEET

PROJECT NO

![](_page_57_Figure_0.jpeg)

![](_page_58_Figure_0.jpeg)

ENGINEERING | ARCHITECTURE | SURVEYING

FUNDING | PLANNING | ENVIRONMENTAL 1230 South Boulevard, Baraboo WI 53913 (608) 356-2771 www.msa-ps.com

		NC	DATE	REVISION	BY	_
PROJECT DATE: .	DRAWN BY: Ir	t.				
	DESIGNED BY: In	it .		· _		
	CHECKED BY: Ir	t.		. "	· ·	
PLOT DATE: 2/24/2023 10:44 PM G:\21\2	1752\21752001\CADD\	Construct	on Documents	CS512 PRECAST TANK - WEISER W25000 dwg		

BY

NO. DATE

_		
R		
78 .		
٦		
,		
2		
P		
2		
5		
,		
Ś		
Ί		
I		
I		
		PROJECT NO.
	W25000 PRECAST TANK	21752002 SHEET
		CS512

![](_page_59_Figure_0.jpeg)

ENGINEERING | ARCHITECTURE | SURVEYING

FUNDING | PLANNING | ENVIRONMENTAL 1230 South Boulevard, Baraboo WI 53913 (608) 356-2771 www.msa-ps.com

**MSA** 

PROJECT DATE: .	DRAWN BY:	Init	· ·		÷	
	DESIGNED BY:	Init			· _ · _	
	CHECKED BY:	Init			. "	
PLOT DATE: 2/24/2023 10:44 PM, G:\21\2	1752\21752001\CAI	DD\Cons	struction	Documents\	CS513 PRECAST TANK - WEISER W20000.dwg	

NO. DATE

ROJEC

; <u>NS</u>	RE-POUR: DST-POUR:	
SER	3/16"=1'-0" PF	
TION	CALE: EV. ATE:	
EQUAL	D, RI	
LLONS	DRAWN BY: WCP DATE: 00/00/00 FILE: W20000 HOLDING	
R)	<b>ICRETE</b> Dick, w 54750.	
FIONAL	WIESER CON W3716 US HWY 10 MAIDEN RO 800-325-845	
TED	W20000 HOLDING SEPTIC MANUAL	
	SHEET NO. 1 OF 1	

	PROJECT NO. 21752002
W20000 FRECAST TANK	SHEET CS513

# SHAFT CONNECTORS FOR PVC-KG DRAINAGE PIPES

![](_page_60_Picture_1.jpeg)

# KGF-S/B shaft connector for PVC-KG pipe connection

Very good waterproof adhesion to the surrounding concrete due to the profiling and textured surface. Easy introduction of the pipe guaranteed (angle ±3"). High impact resistance and low weight. The seals approved, for KG pipes are used.

# Suitable for PVC drainage pipes to DIN EN 1401-1.

Information on the availability of special lengths of KGF-S/B shaft connector is available on request.

DN/OD	dsm _{min}	L	
mm	mm	mm	San da a
110	110,4	80/110/240	And the American Strength Provide Strength
125	125,4	60 / 110 / 240	
160	160,5	65 / 80 / 90 / 110 / 240	
200	200,6	80/110/240	been september
250	250,8	80/110/240	1 No.retarius
315	316,0	80/110/240	
400	401,2	80/110/240	
500	501,5	80/110/240	

![](_page_60_Figure_7.jpeg)

Textured surface

		NO.	DATE	REVISION	BY	
PROJECT DATE: .	DRAWN BY: Ini				÷	
	DESIGNED BY: Ini			· _	÷	
	CHECKED BY: Ini			. "		SIIGA
PLOT DATE: 2/24/2023 10:44 PM G:\21\2	1752\21752001\CADD\C	onstructio	Documents	21752001 - PlanET Details dwg	_	

	PROJECT NO. 21752002
SHAFT CONNECTOR DETAIL	SHEET CS514

![](_page_61_Figure_0.jpeg)

![](_page_62_Figure_0.jpeg)

![](_page_63_Figure_0.jpeg)

![](_page_64_Figure_0.jpeg)

![](_page_65_Figure_0.jpeg)

			NO.	DATE	REVISION	BY	_	
IECT DATE: .	DRAWN BY:	Init						EUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY:	Init			· _		((0)) MSA	1230 South Boulevard, Baraboo WI 53913
	CHECKED BY:	Init	•		· •			(608) 356-2771 www.msa-ps.com
DATE: 2/24/2023 10:44 PM, G:l21/21752/21752001/CADD/Construction Documents/CS518 FLUSH TANK - WALL DETAIL.dwg								© MSA Professional Services, Inc.

BROOKS FARMS DAIRY, LLC WAUPACA COUNTY, WI

*5	LAB LENGTH OR D	#5 @ 13" ISTANCE BETWEEN	#5 @ 9"	#5 @ 7.5" JOINTS IN SLAB.		12	#5 © 13"	
	12	#4 @ 8"	#4 @ 5"	#4 @ 5"			#5 @ 16" #4 @ 8"	
	10	#5 @ 16"	a 16" #5 @ 11" #5 @ 9"			10	#4 @ 10"	
	(INCHES)	<100' #4 @ 10"	<150' #4 @ 7"	<175' #4 @ 6"		(INCHES)	AND SPACING	
SL	AB THICKNESS (INCHES)	SL	AB LENGTH	*	SLAP	TANKS 12' C	REBAR SIZE (GR 1	
REI	NFORCING STEE	L FOR SLABS REBAR SIZE	IN THE "LC (GR 60) A	NG" DIRECTION	REIN	REINFORCING STEEL FOR TANK SLABS IN THE "SHORT" DIRECTION		
7.	TANK BOTTOM	SLAB REINFO	RCEMENT (D	ESIGNED TO ACI 31	B CRITERIA)	R GREATER T	HAN THE FOLLOWING	
	*ANY PRECAST	COMPONENTS	S SHALL BE	DESIGNED FOR	THE MAXIMU	M LOADING C	ONDITIONS ANTICIPAT	
	DRIVE THE	ROUGH PANEL	- 9 1/2"					
	SLATS FO	R EQUIPMENT	- 9 1/2"					
	SLATS FO	R LIVESTOCK	- 6*					
6.	TYPICAL PREC	AST LID THICK	NESSES					
	TS — N NA — N	O ADDITIONAL OT APPLICABL	STEEL NEE E COMBINAT	DED ION OF THICKNE	SS AND HEI	SHT		
	<u> </u>	1 005		1 10 0 0	1 100		1 110 0 0	
	10'	#5 @ 6" NA	#5 @ 8 NA	3″ #5@10 #5@6*	″ <u>#4 @ €</u> NA	5" #4 @ NA	8" #4 @ 10" #5 @ 9"	
	8'	#4 @ 6"	#4 @	10" TS	#4 ⊚ 1	0" #4 @	15" TS	
	HEIGHT 7'	≤ 8″ #4 @ 10′	10" NA	12" NA	#4 @ 1	2" NA	12" NA	
	WALL	0	GRADE	40	_	GRADE	60	
				WITH	SURCHARGE			
	14	#0 @ 5	1 #5 @ (	0   #0@C	11 #5 @ 6	, j#J@		
	10'	#5 @ 8"	#5 @ /	10' TS 6" #5 m #	#5@1	2' #4 @ "#5 @	10" TS 10" #5 @ 12"	
	8'	#4 @ 10'	#4 @	14" TS	#4 @ 1	6" #4 @	18" TS	
	7'	#4 @ 12	' NA	NA	#4 @ 1	8" NA	NA	
	HEIGHT	\$ 8"	10"	12"	8"	10	" 12"	
	CKA		GRADE	40		GRADE	60	

ſ	8. <u>FOOTIN</u> (DESIGNE	IG/WALL HOC	IK BARS CRITERIA)			
			N	0 TR	ACTOR	R ADJACEN
			GRAD	E 40		GR
	WALL HEIGHT (FEET)	WALL THICKNESS (INCHES)	HOOK BAR SIZE	R	S (in)	HOOK BA
	7 OR LESS	8	4	19	8	4
	8	8	4	19	8	4
	8	12	4	21	8	4
	10	8	4	19	8	4
	10	10	4	19	8	4
	10	12	4	21	8	4
	12	12	4	21	8	4
			R			
	JSDA Natural Res	United State Department Agriculture	es : of client	RECE	EPTIC	N TANK
Ċ	Conservatio	on Service	COUNT	Y: <u>W</u>	aupa	ca

		N	IO.	DATE	REVISION	BY	_	
PROJECT DATE: .	DRAWN BY: Ir	it						FUNDING   PLANNING   ENVIRONMENTAL
	DESIGNED BY: In	it			· _			1230 South Boulevard, Baraboo WI 53913
	CHECKED BY: In	it						(608) 356-2771 www.msa-ps.com
PLOT DATE: 2/24/2023 10:44 PM, G:\21121752\21752001\CADDIConstruction Documents\CS518 FLUSH TANK - WALL DETAIL.dwg								© MSA Professional Services, Inc.

2022 EQIP WASTE STORAGE FACILITY
BROOKS FARMS DAIRY, LLC
WAUPACA COUNTY, WI

	LOADING									
٩T	TRACTOR ADJACENT									
ADE 60			GRAD	GRAD	DE 60					
R	R (in)	S (in)	HOOK BAR SIZE	R (in)	S (in)	HOOK BAR SIZE	R (in)	S (in)		
	22	8	4	19	8	4	22	8		
	22	8	4	19	8	4	22	8		
	24	8	4	21	8	4	24	8		
	22	8	4	19	8	4	24	8		
	22	8	4	19	8	4	22	8		
	24	8	4	21	8	4	24	8		
	24	8	5	22	10	5	28	10		

![](_page_66_Figure_5.jpeg)

DESIGN	Date Designed MSA	File Name W1-741D
	Drawn	Date 03/2019
	Approved	

	PROJECT NO. 21752002
FEOSIT TAINE DETAILS	SHEET CS520

			RECEPTION TA	NK DESIGN		
			(DESIGNED TO ACI	318 CRITERIA)		
1. VERTI	CAL WALL STEEL					
Г	WALL	WALL	NO TRACTO		DING TRACTOR	AD JACENT
	HEIGHT	THICKNESS	GRADE 40	GRADE 60	GRADE 40	GRADE 60
	7 FT. or less	8"	#4 @ 12"	#4 @ 18"	#4 @ 10"	#4 @ 16"
-	8 FT.	8"	#4 @ 12"	#4 @ 18"	#4 @ 7"	#5 @ 18"
-	8 FL.	8"	#4 @ 18	#4 @ 18	#4 @ 12 #6 @ 9"	#4 @ 18 #6 @ 12"
-	10 FT.	10"	#5 @ 12"	#4 @ 12"	#5 @ 9"	#5 @ 12"
	10 FT.	12"	#4 @ 9"	#4 @ 15"	#4 @ 7"	#4 @ 10"
L	12 FT.	12"	#5 @ 9"	#5 @ 12"	#6 @ 9"	#6 @ 15"
3. <u>LID S</u>	TEEL (8" THIC (DESIGNED	CK POURED IN	PLACE LID) ERIA)	/		
3. <u>LID S</u>	IEEL (8" THIC (DESIGNET LOADING	CK POURED IN to aci 318 crit - 1. LIVESTO 2. SKID-ST 3. TRACTOF	PLACE LID) ERIA) CK (125 psf) TEER LOADER (1: R (2-5000LB, LC LOADING	50 pst) DACS - 4FT. 0.0 (GRADE 40)	2.)	]
3. <u>LID S</u>	TEEL (8" THIC (DESIGNEI LOADING WIDTH 6 FT.	CK POURED IN 1 TO ACI 318 CRIT 2 SKID-ST 3. TRACTOF 1 #4 @ 12	PLACE LID) ENA) CK (125 psf) TEER LOADER (11 R (2-5000LB, LO LOADING 2 #4 @ 10"	50 pst) DACS - 4FT. 0.0 (GRADE 40) #4 @ 4" 0	) 3 r #5 @ 6"	
3. <u>LID S</u>	WIDTH 6 FT. 8 FT.	CK POURED IN to AcI 318 CRIT - 1. LIVESTO 2. SKID-SI 3. TRACTOF 1 #4 @ 12 #4 @ 12"	PLACE LID) ERNA) CK (125 psf) TEER LOADER (11: R (2-5000LB, LOADING LOADING 2 #4 @ 10" #4 @ 11"	50 ps#) )ALS - 4FT. 0.0 (GRADE 40) #4 ⊕ 4" o #5 ⊕ 4" o	%) 7 <u>#5 @ 6"</u> 7 <u>#6 @ 6"</u>	
3. <u>LID S</u>	WIDTH 6 FT. 10 FT.	K         POURED IN           D TO ACI 318 CRI         1318 CRI           2.         Skilo-Si           3.         TRACTOF           1         12           #4 @ 12"         14           #4 @ 7"         7	PLACE LID) ENA) CK (125 psf) TEER LOADER (11 R (2-5000LB, LO LOADING 44 @ 10" #4 @ 10" #4 @ 10"	50 pst) DACS - 4FT. 0.0 (GRADE 40) #4 ⊕ 4" 0 #5 ⊕ 4" 0 #6 ⊕ 4" 0 #7 ⊕ 4" 0		
3. <u>LID S</u>	WIDTH         6         FT.           10         FT.         10         FT.           12         FT.         FT.         FT.	CK         POURED IN           0 TO ACI 318 CRI         1318 CRI           1         LUXESTO           2         Skilo-Si           3         TRACTOF           1         #4 © 12"           #4 © 12"         #4 © 7"           #6 © 11"         "	PLACE LID) ERIA) CK (125 psf) TEER LOADER (11 R (2-5000LB. LO LOADING 2 #4 @ 10" #4 @ 11" #4 @ 7" #6 @ 10"	50 pst) $\Delta LS - 4FT. 0.0$ (GRADE 40) $\frac{#4 \oplus 4^{*}}{45 \oplus 4^{*}} \circ$ $\frac{#6 \oplus 4^{*}}{47} \circ$ $\frac{#7 \oplus 4^{*}}{47} \circ$	2) r <u>#5</u> @ 6" r <u>#6</u> @ 6" r <u>#7</u> @ 5" r <u>#8</u> @ 4"	
3. LID S	WIDTH 6 FT. 10 FT. 12 FT.	CK POURED IN D TO ACI 318 CRT 2. SKID-ST 3. TRACTOF 1 #4 ⊕ 12 #4 ⊕ 12" #4 ⊕ 7" #6 ⊕ 11"	PLACE LID) ERIA) CK (125 psf) TEER LOADER (11 R (2-5000LB. LO LOADING #4 @ 10" #4 @ 11" #4 @ 7" #6 @ 10"	50 pst) $\Delta E^{S} - 4FT. 0.0$ (GRADE 40) $\frac{\#4 \oplus 4^{*}}{\#5 \oplus 4^{*}} \circ$ $\frac{\#6 \oplus 4^{*}}{\#7 \oplus 4^{*}} \circ$ (GRADE 60)	2.) r <u>#5</u> @ 6" r <u>#6</u> @ 6" r <u>#7</u> @ 5" r <u>#</u> 8 @ 4"	
3. LID S	WIDTH WIDTH 6 FT. 8 FT. 10 FT. 12 FT. WIDTH	CK POURED IN D TO ACI 318 CRT 2. SKID-ST 3. TRACTOF #4 © 12" #4 © 12" #4 © 7" #6 © 11"	PLACE LID) ERIA) CK (125 psf) TEER LOADER (11 R (2-5000LB. LO LOADING #4 @ 10" #4 @ 11" #4 @ 7" #6 @ 10" LOADING 2	50 pst) $\Delta CS - 4FT. 0.0 (GRADE 40) \frac{1}{4}4 \oplus 4^{*} 0\frac{1}{4}5 \oplus 4^{*} 0\frac{1}{4}6 \oplus 4^{*} 0\frac{1}{4}7 \oplus 4^{*} 0(GRADE 60)$	2.) r <u>#5</u> @ 6" r <u>#6</u> @ 6" r <u>#7</u> @ 5" r <u>#</u> 8 @ 4" 3	
3. <u>LID S</u>	WIDTH 6 FT. 12 FT. WIDTH 6 FT. 10 FT. 12 FT. WIDTH 6 FT.	K       POURED IN         0       10 ACI 318 CRIN         :       - 1. LIVESTOI         2. SKID-SI         3. TRACTOF         1         #4 @ 12"         #4 @ 12"         #4 @ 7"         #6 @ 11"         #6 @ 12"         #4 @ 12"         #4 @ 7"         #6 @ 11"	PLACE LID) ERIA) CK (125 psf) TEER LOADER (11 R (2-5000LB. LO LOADING 2 #4 @ 10" #4 @ 11" #6 @ 10" LOADING 2 #4 @ 12"	50 pst) $\Delta CS - 4FT. 0.0$ (GRADE 40) $\frac{#4 \oplus 4^{*}}{15 \oplus 4^{*}} \circ$ $\frac{#6 \oplus 4^{*}}{17 \oplus 4^{*}} \circ$ (GRADE 60) $\frac{#3 \oplus 4^{*}}{100} \circ$	2) 7	
3. <u>LID S</u>	WIDTH         6         FT.           10         FT.         12           WIDTH         6         FT.           10         FT.         12           WIDTH         6         FT.           8         FT.         12	K       POURED IN         D TO ACI 318 CRIM         I = 1. LUVESTOI         2. SKID-SI         3. TRACTOF         1         #4 @ 12"         #4 @ 7"         #6 @ 11"         #/4 @ 12"         #/4 @ 12"         #/4 @ 12"         #/4 @ 12"         #/4 @ 12"	PLACE LID) ERIA) CK (125 psf) FEER LOADER (11 R (2-5000LB. LO LOADING 2 #4 @ 10" #4 @ 11" #6 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 12"	50 pst) $\Delta CS - 4FT. 0.0$ (GRADE 40) $\frac{#4 \oplus 4^{*} \text{ o}}{#5 \oplus 4^{*} \text{ o}}$ $\frac{#6 \oplus 4^{*} \text{ o}}{#7 \oplus 4^{*} \text{ o}}$ (GRADE 60) $\frac{#3 \oplus 4^{*} \text{ o}}{#4 \oplus 4^{*} \text{ o}}$	3 r <u>#5</u> @ 6" r <u>#6</u> @ 6" r <u>#7</u> @ 5" r <u>#8</u> @ 4" 3 r <u>#4</u> @ 6" r <u>#5</u> @ 6" r <u>#5</u> @ 6"	
3. <u>LID S</u>	WIDTH         6         FT.           10         FT.         10           12         FT.         10           8         FT.         10           10         FT.         12           10         FT.         12           10         FT.         12           9         FT.         10           10         FT.         12	K       POURED IN         D TO ACI 318 CRIM         I = 1. LIVESTO         2. SKID-SI         3. TRACTOF         #4 @ 12"         #4 @ 12"         #4 @ 7"         #6 @ 11"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 12"         ## @ 11"         #5 @ 12"	PLACE LID) ERNA) CK (125 psf) TERE LOADER (11: R (2-5000LB. LG LOADING #4 @ 10" #4 @ 10" #6 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 10" #4 @ 10"	50 pst) $\Delta RS - 4FT. 0.0$ (GRADE 40) $\frac{#4 \oplus 4^{\prime\prime}}{15 \oplus 4^{\prime\prime}} \circ$ $\frac{#6 \oplus 4^{\prime\prime}}{17 \oplus 4^{\prime\prime}} \circ$ (GRADE 60) $\frac{#3 \oplus 4^{\prime\prime}}{14 \oplus 4^{\prime\prime}} \circ$ $\frac{#5 \oplus 4^{\prime\prime}}{15 \oplus 4^{\prime\prime}} \circ$	$\begin{array}{c} 3 \\ r & \#5 @ 6'' \\ r & \#6 @ 6'' \\ r & \#7 @ 5'' \\ r & \#8 @ 4'' \\ \hline \\ 3 \\ r & \#4 @ 6'' \\ r & \#6 @ 6'' \\ r & \#6 @ 6'' \\ r & \#6 @ 6 & 4'' \\ \end{array}$	
3. <u>LID S</u>	WIDTH         6         FT.           10         FT.         12           WIDTH         6         FT.           10         FT.         12           112         FT.         10           10         FT.         12           112         FT.         10	K POURED IN 10 TO ACI 318 CRM = 1. LUVESTO 2. SKID-SI 3. TRACTOF 44 © 12" $\frac{4}{4}$ © 12" $\frac{4}{4}$ © 0.11" $\frac{4}{6}$ © 11" $\frac{4}{4}$ © 12" $\frac{4}{4}$ © 12" $\frac{4}{4}$ © 12" $\frac{4}{4}$ © 12" $\frac{4}{4}$ © 12" $\frac{4}{5}$ © 12"	PLACE LID) ERIA) CK (125 psf) FEER LOADER (11 R (2-5000LB. LO LOADING 2 #4 @ 10" #4 @ 10" #6 @ 10" #6 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 12" #4 @ 10" #5 @ 11"	50 pst) $\Delta CS - 4FT. 0.0$ (GRADE 40) $\frac{#4 \oplus 4^{\prime\prime}}{F5 \oplus 4^{\prime\prime}} \circ 0$ $\frac{#6 \oplus 4^{\prime\prime}}{F7 \oplus 4^{\prime\prime}} \circ 0$ $\frac{#7 \oplus 4^{\prime\prime}}{F7 \oplus 4^{\prime\prime}} \circ 0$ (GRADE 60) $\frac{#3 \oplus 4^{\prime\prime}}{F5 \oplus 4^{\prime\prime}} \circ 0$ $\frac{#5 \oplus 4^{\prime\prime}}{F5 \oplus 3^{\prime\prime}} \circ 0$	$\begin{array}{c} 3 \\ r & \#5 & @ & 6'' \\ r & \#6 & @ & 6'' \\ r & \#7 & @ & 5'' \\ r & \#8 & @ & 4'' \\ \end{array}$ $\begin{array}{c} 3 \\ r & \#4 & @ & 6'' \\ r & \#5 & @ & 6'' \\ r & \#6 & @ & 6'' \\ r & \#6 & @ & 6'' \\ r & \#6 & @ & 4'' \\ \end{array}$	
3. LID S	WIDTH         6         FT.           10         FT.         12           WIDTH         6         FT.           10         FT.         12           112         FT.         10           10         FT.         12           112         FT.         10	K       POURED IN         D       TO ACI 318 CRIN         I       LVESTO         2. SKID-ST         3. TRACTOF         #4       12"         #4       12"         #4       12"         #6       11"         #7       #4         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #5       12"	PLACE LID) ERIA) CK (125 psf) TERE LOADER (11 R (2-5000LB. LG LOADING #4 ⊕ 10" #4 ⊕ 10" LOADING 2 #4 ⊕ 12" #4 ⊕ 12" #4 ⊕ 12" #4 ⊕ 10" #5 ⊕ 11"	50 pst) ACS - 4FT. 0.0 (GRADE 40) $\frac{#4 \oplus 4^{n}}{5 \oplus 4^{n}} \oplus \frac{4^{n}}{6} \oplus \frac{4^{n}}{4^{n}} \oplus \frac{4^{n}}{6} \oplus 4^{n$	$\begin{array}{c} 3 \\ r & \#5 & \textcircled{o} & \textcircled{o}'' \\ r & \#6 & \textcircled{o} & \textcircled{o}'' \\ r & \#7 & \textcircled{o} & 5'' \\ r & \#8 & \textcircled{o} & 4'' \\ \end{array}$ $\begin{array}{c} 3 \\ r & \#4 & \textcircled{o} & \textcircled{o}'' \\ r & \#5 & \textcircled{o} & \textcircled{o}'' \\ \#6 & \textcircled{o} & 4'' \\ \end{array}$	
	WIDTH         6 FT.           8 FT.         10 FT.           12 FT.         12 FT.	K       POURED IN         D       TO ACI 318 CRIN         I       LIVESTOI         2. SKID-SI         3. TRACTOF         #4       12"         #4       12"         #6       11"         #7       €         #4       12"         #4       0         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"	PLACE LID) ERIA) CK (125 psf) TERE LOADER (11 R (2-5000LB. LG LOADING #4 ⊕ 10" #4 ⊕ 10" #6 ● 10" LOADING 2 #4 ⊕ 12" #4 ⊕ 12" #4 ⊕ 12" #4 ⊕ 10" #5 ⊕ 11"	50 pst) $ACS - 4FT. 0.0 (GRADE 40) \frac{1}{14} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{17} \oplus 4^{n} o\frac{1}{17} \oplus 4^{n} o\frac{1}{13} \oplus 4^{n} o\frac{1}{14} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o$	$\begin{array}{c} 3 \\ r & \#5 & \textcircled{m} & 6'' \\ r & \#6 & \textcircled{m} & 6'' \\ r & \#7 & \textcircled{m} & 5'' \\ r & \#8 & \textcircled{m} & 4'' \\ \end{array}$ $\begin{array}{c} 3 \\ r & \#4 & \textcircled{m} & 6'' \\ r & \#5 & \textcircled{m} & 6'' \\ r & \#6 & \textcircled{m} & 6'' \\ r & \#6 & \textcircled{m} & 4'' \\ \end{array}$	Dote File Norr
	United State	K       POURED IN         D TO ACI 318 CRIM         S       TRACTOF         3. TRACTOF         #4       12"         #4       12"         #6       11"         #6       12"         #4       12"         #4       12"         #6       11"         #5       12"	PLACE LID) ERIA) CK (125 psf) TERE LOADER (11 R (2-5000LB. LG LOADING 2 #4 @ 10" #4 @ 10" #6 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 12" #4 @ 10" #5 @ 11"	50 p3f) $DACS - 4FT. 0.0 (GRADE 40) \frac{1}{14} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{17} \oplus 4^{n} o\frac{1}{17} \oplus 4^{n} o\frac{1}{14} \oplus 4^{n} o\frac{1}{14} \oplus 4^{n} o\frac{1}{14} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{15} \oplus 4^{n} o\frac{1}{15} \oplus 3^{n} oDESIGN$	<ul> <li>3         <ul> <li>7</li></ul></li></ul>	Date File Nam WI-741A
3. LID S	VIDTH 6 FT. 8 FT. 10 FT. 12 FT. WIDTH 6 FT. 8 FT. 10 FT. 12 FT. United State Department Agriculture	K       POURED IN         D TO ACI 318 CRIM         I = 1. LUVESTOI         2. SKID-SI         3. TRACTOF         1         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #4 @ 12"         #5 @ 12"         #6 @ 11"	PLACE LID) ERIA) CK (125 psf) TERE LOADER (11: R (2-5000LB, LG 2 #4 @ 10" #4 @ 10" LOADING 2 #4 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 12" #4 @ 11" ECORDING 2 #4 @ 11" #5 @ 11"	50 p3t) DACS - 4FT. 0.0 (GRADE 40) #4 ⊕ 4" oo #6 ⊕ 4" oo #7 ⊕ 4" oo #7 ⊕ 4" oo #7 ⊕ 4" oo #4 ⊕ 4 oo #5 ⊕ 4" oo #4 ⊕ 4 oo #5 ⊕ 3" oo DESIGN	2.) 7	Date File Nam WI-741A Date Date
	VIDTH 6 FT. 8 FT. 10 FT. 12 FT. WIDTH 6 FT. 8 FT. 10 FT. 12 FT. United State Department Agriculture OCOURCOC	K       POURED IN         0       10 ACI 318 CRIN         i =       1. LIVESTO         2. SKID-SI         3. TRACTOF         #4       12"         #4       12"         #4       0         #4       0         #4       12"         #4       0         #4       12"         #4       12"         #4       12"         #4       12"         #4       12"         #5       12"         #5       12"         Sof       REC         CLIENT:       B	PLACE LID) ERNA) CK (125 psf) TERE LOADER (11: R (2-5000LB. LG LOADING 2 #4 @ 10" #4 @ 11" #6 @ 10" LOADING 2 #4 @ 12" #4 @ 12" #4 @ 12" #4 @ 11" CADING 2 EDADING 2 COMPACTOR (12) COMPACTOR (12) COMPA	50 p3t) DACS - 4FT. 0.0 (GRADE 40) #4 ⊕ 4" 0 #6 ⊕ 4" 0 #7 ⊕ 4" 0 #7 ⊕ 4" 0 #7 ⊕ 4" 0 (GRADE 60) #3 ⊕ 4" 0 #4 ⊕ 4 0 #5 ⊕ 4" 0 #5 ⊕ 3" 0 DESIGN	3         r       #5       ©       6"         r       #6       ©       6"         r       #7       ©       5"         r       #8       @       4"         3	Date File Nam WI-741A Date 03/2019

	RA STEEL (C OCATED IN TOP DESIGNED TO ACL 3	RADE 40) (GI	RADE_60) R SLAT OR BE	AM & SLAT TA	NK				
		ne entenary							
			WALL	UEICUT	ET				
	WALL		WALL	SPAN ALONG	TOP OF W	ALL			
	THICKNESS	8	FT.	10	FT.	12	FT.		
		GRADE 40	GRADE 60	GRADE 40	GRADE 60	GRADE 40	GRADE 60		
	8"	3 - #6	3 - #5	3 - #7	4 - #5	4 - #8	4 - #7		
		4 - #5	2 - #6	4 - #6	3 - #6				
	10"	3 - #5	3 - #4	3 - #6	4 - #4	3 - #7	4 - #5		
	10"	4 - #4	2 - #5	4 - #5	3 - #5	4 - #6	3 - #6		
	12	5 - #4	2 - #4	3 - #5	2 - #C	5 - #6	2 - #6		
			WALL	HEIGHT - 10	FT.	and the second s			
	WALL			SPAN ALONG	TOP OF W	ALL			
	THICKNESS	8	FT.	10	FT.	12	FT.		
		GRADE 40	GRADE 60	A - 48	A - #6	THICKEN	GRADE 60		
	8"	4 - 40	3 - #6		4 - 80	WALL	WALL		
		3 - #6	3 - #5	3 - #7	4 #5	4 - #8	4 - #6		
	10"	4 - #5	2 - #6	4 - #6	3 - #6				
	12"	2 - #6	2 - #5	2 - #8	2 - #6	3 - #8	3 - #6		
	12	3 - #5		3 — #6		4 - #7			
		WALL HEIGHT - 12 FT							
		-	WALL	HEIGHT - 12	FT.				
	WALL		WALL	HEIGHT - 12 SPAN ALONG	FT. TOP OF W	ALL			
	WALL THICKNESS	8	FT.	HEIGHT - 12 SPAN ALONG 10	FT. TOP OF W		FT.		
	WALL THICKNESS	GRADE 40	FT. GRADE 60	HEIGHT - 12 SPAN ALONG 10 GRADE 40	FT. TOP OF WA	ALL 12 D GRADE 40	FT. GRADE 60		
	WALL THICKNESS	8 GRADE 40 4 - #7	WALL FT. GRADE 60 4 - #6	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WAT	FT. TOP OF W FT. GRADE 60 THICKEN	AL 12 D GRADE 40 I THICKEN WALL	FT. GRADE 60 THICKEN WALL		
	WALL THICKNESS 8*	8 GRADE 40 4 - #7 3 - #7	WALL FT. GRADE 60 4 - #6 4 - #5	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8	FT. TOP OF W. FT. CRADE 60 THICKEN WALL 4 - #6	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN	FT. GRADE 60 THICKEN WALL THICKEN		
	WALL THICKNESS 8" 10"	8 GRADE 40 4 - #7 3 - #7 4 - #6	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8	FT. TOP OF W FT. GRADE 60 THICKEN WALL 4 - #6	ALL 12 D GRADE 40 I THICKEN WALL THICKEN WALL	FT. GRADE 60 THICKEN WALL THICKEN WALL		
	WALL THICKNESS 8" 10"	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 2 - #6	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8	FT. TOP OF W. FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
	WALL THICKNESS 8" 10" 12"	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 2 - #6	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - ≢8 3 - ≢8	FT. TOP OF W. FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
	WALL THICKNESS 8" 10" 12"	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 2 - #6	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8	FT. TOP OF W. FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL 12 GRADE 40 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
ONST	WALL THICKNESS 8" 10" 12" RUCTION NOTES	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 FOR SLAT A	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 2 - #6 ND BEAM & S	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS;	FT. TOP OF W. FT. GRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL 12 GRADE 40 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - ∰7		
ONSTI	WALL THICKNESS 8" 10" 12" RUCTION NOTES RUCTION NOTES	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 FOR SLAT A ALWAYS REQU	WALL           FT.           GRADE         60           4         −           4         −           5         3           7         #6           8         −           8         −           0         0           4         −           4         −           60         −           7         −           8         −           8         −           8         −           8         −           9         0           9         0           9         0	HEIGHT - 12 SPAN ALONG GRADE 40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS: ALLS: MALE MALE	FT. TOP OF W. FT. CRADE 60 THICKEN WALL 4 - #6 3 - #6	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - ∦8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 — ∰7		
ONSTI	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS CTRA STEEL IS CTRA STEEL IS CTRA STEEL IS CTRA STEEL IS	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 FOR SLAT A ALWAYS REQU ALWAYS REQU ALWAYS REQU	WALL           FT.           GRADE         60           4         - #6           3         - #6           2         - #6           ND         BEAM & S           IRED         AT           ACHED         ND           ACHED         ND	HEIGHT - 12 SPAN ALONG GRADE-40 THICKEN WALL 4 - 48 3 - 48 3 - 48 LAT TANKS; ALLS. WALLS WHEN T TOP OF THE	FT. TOP OF W FT. CRADE 60 THICKEN WALL 4 - #6 	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - ∰7		
ONST EX	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS CTRA STEEL IS D BUILDING FLC D BUILDING FLC	8 GRADE 40 4 - #7 3 - #7 3 - #6 2 - #7 3 - #6 S FOR SLAT A ALWAYS REQU ALWAYS REQU ALWAYS REQU ALWAYS REQU ALWAYS REQU ALWAYS REQU ALWAYS REQU	WALL           FT.           GRADE           60           4 - #6           3 - #6           2 - #6           ND BEAM & S           NIRED AT ENDW           IRED AT ENDW           ACHED TO THE           SHOWN ABOVE	HEIGHT - 12 SPAN ALONG GRADE 40 THICKEN WALL 4 - 48 3 - 48 LAT TANKS; ALLS. WALLS WHEN 1 : TOP OF THE REFERS TO T	FT. TOP OF W. FT. CRADE 6C THICKEN WALL 4 - #6 3 - #6 HERE IS WALL. HE BEAM	ALL 12 0 GRADE 40 1 THICKEN WALL 1 HICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
ONST EX NC SF SF	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS CHARA STEEL IS D BUILDING FLC PAN ALONG TO PACING ALONG TO	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 FOR SLAI A ALWAYS REQU DOR SLAB ATI PO F WALL [®] THE SIDEWALL	WALL           FT.         GRADE 60           4 - #6         #6           3 - #6         #6           2 - #6         #6           ND BEAM & S         SinRED AT ENDWIRED ON SIDENACHED TO THE ACHED TO THE ACHED TO THE SIOWN ABOVE           SHOWN ABOVE         Si AND THE T/	HEIGHT - 12 SPAN ALONG 10 GRADE-40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS; ALLS. WALLS WHEN T : TOP OF THE REFERS TO FTHE TANK WIDTH FO	FT. TOP OF W. FT. GRADE 6C WALL 4 - #6 3 - #6 3 - #6 HERE IS WALL 4 - E BEAM R THE	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
ONSTI . EX NC . "S SF EN	WALL THICKNESS 8" 10" 12" RUCTION NOTESS (TRA STEEL IS CTRA STEEL IS CHAN ALONG TO PAN ALONG TO PAN ALONG TO DUBLA SLAT TAM	8           GRADE         40           4         - #7           3         - #7           4         - #6           2         - #7           3         - #6           5         FOR SLAT A           ALWAYS REQU         DOR SLAB ATT           JP OF WALL"         SLAB ATT           JP OF WALL"         THE SIDEWALL	WALL           FT.         GRADE 60           4 - #6         4           3 - #6         4           Ø - #6         60           Ø - #6         8           ND BEAM & S         3           IRED AT ENDWIRED ON SIDEL         ACHED TO THE           SHOWN ABOVE         55, AND THE TI	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS: ALLS. WALLS WHEN T TOP OF THE REFERS TO T REFERS TO T REFERS TO T	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 HERE IS WALL 16 BEAM R THE	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
ONSTI . EX . EX . SF <u>EN</u> . FO TO	WALL THICKNESS 8" 10" 12" RUCTION NOTESS (TRA STEEL IS D BUILDING FLG DI BUILDING FLG DI BUILDING FLG DI BUILDING FLG DI BUILDING FLG DI BUILT SC ND WALLS. R A SLAT TAN P OF WALL" C	8 GRADE 40 4 - #7 3 - #7 3 - #6 2 - #7 3 - #6 2 FOR SLAT A ALWAYS REQU DOR SLAB ATT POF WALL ⁹ THE SIDEWALL K WITH ND BI	WALL           FT.           GRADE 60           4 - #6           3 - #6           2 - #6           MD BEAM & S           IRED AT ENDWIN           ACHED TO THE           SHOWN ABOVE           S; AND THE TH           EAMS, USE THIN	HEIGHT - 12 SPAN ALONG 10 GRADE 40 THICKEN WALL 4 - #8 3 - #8 3 - #8 LAT TANKS: ALLS. WALLS WHEN 1 TOP OF THE REFERS TO T ANK WIDTH FO E 12 FT *SPAI	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 WALL. 4E BEAM R THE N ALONG THE	ALL 12 GRADE 40 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7		
ONSTI - EX NC - FO EN - FO O 04	WALL THICKNESS 8" 10" 12" RUCTION NOTES CTRA STEEL IS D BUILDING FLC D BUILDING FLC D BUILDING FLC D BUILDING FLC D BUILDING FLC D BUILT ALONG TO DWALLS. DR A SLAT TAN P OF WALL" C StM PLAN: "NEV	8           GRADE 40           4 - #7           3 - #7           4 - #6           2 - #7           3 - #6           S FOR SLAT A           ALWAYS REQU           ALWAYS REQU           ALWAYS REQU           ALWAYS REQU           ALWAYS REQU           ALWAYS REQU           K WITH NO BI           COLUMN ABOVE           K WITH NO BOVE	WALL           FT.           GRADE 60           4 - #6           3 - #6           2 - #6           ND BEAM & S           IRED AT ENDW           IRED AT ENDW           ACHED TO THE           SHOWN ABOVE           S; AND THE T;           EAMS, USE THIS           ADD AD A 3           AORE THAN 3	HEIGHT - 12 SPAN ALONG GRADE-40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS: ALLS. WHEN T REFERS TO T REFERS TO T ANK WIDTH FO E 12 FT *SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - ∦8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 — ∰7		
ONSTI EX NC SF EN TO Od Of	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS CTRA STEEL IS CTRA STEEL IS DE BUILDING FL SPAN ALONG TO SPAN ALONG TO SPAN ALONG TO PO F WALL" C PO WALL" C ME A SLAT TAN OP OF WALL" C SM PLAN: "NEW NE TIME FOR A	8           GRADE 40           4 - #7           3 - #7           4 - #6           2 - #7           3 - #6           S FOR SLAT A           ALWAYS REQU           CON RUAL           CHE REMOVE N           NY REASON."	WALL FT. GRADE 60 4 - #6 3 - #6 2 - #6 ND BEAM & S IRED AT ENDW IRED ON SIDEH ACHED TO INDEH SHOWN ABOVE S, AND THE T. EAMS, USE THA A AD AD A 3 AORE THAN 3	HEIGHT - 12 SPAN ALONG 10 GRADE-40 THICKEN WALL 4 - 48 3 - 48 3 - 48 LAT TANKS; ALLS. WHEN T REFERS TO T ANK WIDTH FO E 12 FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 WALL 4E BEAM R THE V ALONG THE TS AT	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - ∰7		
ONSTI EX EX SF EN FO O 0 0 0 0	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS D BUILDING FLC ACING ALONG TO PACING ALONG TO PACING ALONG TO ACING ALONG ALONG ALONG ALONG TO ACING ALONG ALON	8 GRADE 40 4 - #7 3 - #7 4 - #6 2 - #7 3 - #6 5 FOR SLAT A ALWAYS REQU ALWAYS REQU ALW	WALL FT. GRADE 60 4 - #6 3 - #6 2 - #6 ND BEAM & S IRED AT ENDW IRED ON SIDEY ACHED TO THE SHOWN ABOVE SHOWN ABOVE SHOWN ABOVE SHOWN ABOVE SHOWN ABOVE SHOWN ABOVE SHOWN ABOVE ACHED TO THE SHOWN ABOVE SHOWN A	HEIGHT - 12 SPAN ALONG GRADE 40 THICKEN WALL 4 - 48 3 - 48 ALAT TANKS; ALLS. WALLS WHEN T TOP OF THE TOP OF THE TO	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 3 - #6 WALL 4E BEAM R THE N ALONG THE IS AT	ALL 12 0 GRADE 40 1 THICKEN WALL 1 HICKEN WALL 4 - #8	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7 Dote		
CONSTI . EX . EX . EX . FO . FO . FO . ON	WALL THICKNESS 8" 10" 12" RUCTION NOTESS (TRA STEEL IS D BUILDING FLC PAR ALONG TO PARA STEEL IS D BUILDING FLC PARA ALONG TO PARA STAT TAN OP OF WALL" C %M PLAN: "NEV NE TIME FOR A United Sta	8           GRADE 40           4 - #7           3 - #7           4 - #6           2 - #7           3 - #6           S. FOR SLAT A           ALWAYS REQU           DOR SLAB ATT           PO FF WALL*'S           THE SIDEWALL           K WITH NO BI           CUUMN ABOVE *           NY REASON."	WALL FT. GRADE 60 4 - #6 3 - #6 3 - #6 A - #5 3 - #6 A - #6 A - #5 A - #6 A - #6	HEIGHT - 12 SPAN ALONG 10 GRADE-40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS; ALLS. WALLS WHEN T TO OF THE REFERS TO FTHE TANK WIDTH FO E 12 FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 HERE IS WALL. 4 - #6 A - #6 WALL 4 - #6 WALL A - #6 N	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8 esigned MSA	FT. GRADE 60 THICKEN WALL THICKEN WALL 4 - #7 Effe Nam Wi-7418		
CONSTI . EX . EX NC . TO . FO ON . FO ON	WALL THICKNESS 8" 10" 12" RUCTION NOTESS (TRA STEEL IS DEULDING FLC PRAN ALONG TO PACING ALONG TO DEVALONG TO DR A SLAT TAN PO OF WALL" C %M PLAN: "NEV NE TIME FOR A United Sta Departme	8           GRADE 40           4 - #7           3 - #7           4 - #6           2 - #7           3 - #6           S FOR SLAT A           ALWAYS REQU           DOR SLAB ATT           ALWAYS REQU           DOR SLAB ATT           POF WALL*           THE SIDEWALL           K WITH NO BOY           CULUMN ABOY           CICULMN ABOY           CULUMN ABOY           FREMOVE N           NY REASON.*           ates           nt of	WALL FT. GRADE 60 4 - #6 4 - #5 3 - #6 A	HEIGHT - 12 SPAN ALONG 10 GRADE-40 GRADE-40 THICKEN WALL 4 - #8 3 - #8 ALLS. WALLS WHEN T TOP OF THE REFERS TO FTHE TANK WIDTH FO E 12 FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 WALL. 4 - #6 WALL. 4 - #6 WALL. 4 - #6 WALL. 1 - #6 WAL	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - #8 4 - #8 4 - #8	FT.         GRADE 60           THICKEN         WALL           THICKEN         WALL           4         - #7		
CONSTI EX EX NC NC NC NC NC NC NC NC NC NC	WALL THICKNESS 8" 10" 12" RUCTION NOTES (TRA STEEL IS CTRA STEEL IS CTRA STEEL IS OB BUILDING FL PAN ALONG TO PACING ALONG DE BUILDING FL DE	8           GRADE 40           4 - #7           3 - #7           4 - #6           2 - #7           3 - #6           S FOR SLAT A           ALWAYS REQU           ALWAYS REQU           ALWAYS REQU           AUWAYS REQU           AUWAYS REQU           CR SLAB ATT           P OF WALL"           YTHE SIDEWALL           K WITH NOB BIO           CER REMOVE N           NY REASON."           ates           nt of	WALL FT. GRADE 60 4 - #6 4 - #6 3 - #6 2 - #6 ND BEAM & S IRED AT ENDW IRED ON SIDET IRED AT ENDW IRED ON SIDET SHOWN ABOVE S; AND THE T, EAMS, USE THIS AO(HE) TO THE SHOWN ABOVE S; AND THE T, EAMS, USE THIS AO(HE) TO THE AND ADD A 3 INFO ADD A 3 INFO ADD A 3 INFO ADD A 5 INFO ADD A 5	HEIGHT - 12 SPAN ALONG GRADE-40 THICKEN WALL 4 - #8 3 - #8 LAT TANKS: ALLS. WALLS WHEN T TOP OF THE REFERS TO T ANK WIDTH FO E 12 FT "SPAI STATEMENT IN ADJACENT SLA	FT. TOP OF W. FT. GRADE 6C THICKEN WALL 4 - #6 3 - #6 HERE IS WALL. 4 - #6 WALL. 4 - #6 MALONG THE N ALONG THE N D D	ALL 12 0 GRADE 40 1 THICKEN WALL THICKEN WALL 4 - ∦8 esigned MSA rown	FT.         GRADE         60           THICKEN         WALL         THICKEN           WALL         THICKEN         WALL           4         - #7		

		NO.	DATE	REVISION	BY	_		
PROJECT DATE: .	DRAWN BY: Init						FUNDING   PLANNING   ENVIRONMENTAL	4
	DESIGNED BY: Ini			· _	· •		1230 South Boulevard, Baraboo WI 53913	
	CHECKED BY: Ini					SIICA	(608) 356-2771 www.msa-ps.com	
PLOT DATE: 2/24/2023 10:44 PM, G:\21\21752\21752001\CADD\Construction Documents\CS518 FLUSH TANK - WALL DETAIL.dwg							© MSA Professional Services, Inc.	

	PROJECT NO. 21752002
FLUSH TANK DETAILS	SHEET

![](_page_68_Figure_0.jpeg)

		NO.	DATE	REVISION	BY	_		
PROJECT DATE: .	DRAWN BY: Init						FUNDING   PLANNING   ENVIRONMENTAL	2022 EQIP WASTE STORAGE FACILITY
	DESIGNED BY: Init						1230 South Boulevard, Baraboo WI 53913	BROOKS FARMS DAIRY, LLC
	CHECKED BY: Init						(608) 356-2771 www.msa-ps.com	WALIPACA COUNTY WI
PLOT DATE: 2/24/2023 10:44 PM, G:\21\2	PLOT DATE: 2/24/2023 10:44 PM, G:/21/21752/217552001\CADD\Construction Documents\CS518 FLUSH TANK - WALL DETAIL.dwg					© MSA Professional Services, Inc.		

	PROJECT NO. 21752002
FLUGHTANK DETAILS	SHEET CS522

# **GENERAL REINFORCING/CONCRETE NOTES**

- ALL LAPS SHALL BE CLASS-'B' PER ACI 318, UNLESS NOTED OTHERWISE ON THE DESIGN DRAWINGS, AND THE DETAILER TAKES SPECIAL CARE TO PROVIDE STAGGERED LAPS. USE TOP BAR LAP LENGTHS FOR ALL HORIZONTAL BARS AND FOR BARS IN SLABS WITH MORE THAN 12" OF CONCRETE BELOW. SEE DETAIL 6/S303 FOR REINFORCING SPLICE
- LAP LENGTH SHALL BE SPECIFICALLY NOTED ON PLACING DRAWINGS WHERE MORE THAN ONE BAR MAKES UP A CONTINUOUS STRING. 2.
- BAR PLACEMENT TOLERANCES SHALL BE AS SPECIFIED IN THE CONCRETE REINFORCING STEEL INSTITUTE (CRSI) MANUAL OF STANDARD PRACTICE, CURRENT 3. EDITION
- ALL REINFORCING BARS DIMENSIONS ARE FROM OUT-TO-OUT BAR. ALL BEND ANGLES ARE AT 45 DEGREES AND 90 DEGREES, UNLESS NOTED OTHERWISE. 4.
- ALL JOINTS IN LIQUID RETAINING STRUCTURES SHALL CONTAIN WATERSTOPS AT SLAB/WALL JOINT AND AT ALL CONSTRUCTION AND CONTRACTION JOINTS. SEE DETAILS 1, 2, & 4/S303
- THE READY MIX CONCRETE SUPPLIER SHALL PROVIDE A MIX DESIGN THAT MINIMIZES SHRINKAGE. THIS MIX DESIGN SHALL MINIMIZE THE AMOUNT OF WATER TO 6. 0.45 W/C RATIO, MINIMIZE CONCRETE PASTE, AND USE AGGREGATES OF APPROPRIATE TYPE, SIZE AND GRADATION PER ACI 360 FOR SLABS-ON-GRADE AND ACI 318 FOR WALLS & FOOTINGS.
- WHEN APPLICABLE, GROUT USED TO SEAL AROUND PIPE PENETRATION SHALL BE NON-SHRINK, NON-METALLIC GROUT WITH A COMPRESSIVE STRENGTH EQUAL 7. TO OR GREATER THAN THE COMPRESSIVE STRENGTH OF THE SURROUNDING CONCRETE MEMBER.
- ALL CONCRETE SUBJECT TO EXTERIOR EXPOSURE SHALL BE AIR ENTRAINED, TOTAL AIR CONTENT OF 6% +/- 1%. 8.
- UNLESS THE MIX DESIGN INCLUDES THE USE OF SUPERPLASTICIZERS, CONCRETE WITH A SLUMP GREATER THAN 5" SHALL BE REFUSED. CONCRETE WITH APPROVED SUPERPLASTICIZERS SHALL NOT HAVE A SLUMP OF GREATER THAN 8".
- CALCIUM CHLORIDE AND/OR ADMIXTURES CONTAINING CALCIUM CHLORIDE SHALL NOT BE USED. 10.
- SOME FINE LINE RANDOM SHRINKAGE CRACKING MAY DEVELOP. HOWEVER PER NRCS 313, ACI 318 & PCA, WITH THE USE OF STEEL AS SHOWN THESE CRACKS ARE EXPECTED TO PERFORM AT A WATERTIGHT LEVEL. LARGER WALL AND FLOOR CRACKS DUE TO IMPROPER CURING METHODS, WEATHER PROTECTION, 11. SUBSTITUTION, DELETION OR MISPLACEMENT OF REINFORCEMENT OR IMPROPER MIX DESIGN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 12. PROVIDE ADDITIONAL DIAGONAL REINFORCING AROUND ALL OPENINGS AND PENETRATIONS THROUGH WALLS AND SLABS SEE DETAIL 5/S303

## **GENERAL STRUCTURAL/FOUNDATION NOTES**

JECT DATE

1/11/2023 DRAWN BY: BLS

DESIGNED BY: MLB

CHECKED BY: SHG

- CONTRACTOR TO COORDINATE STRUCTURAL AND CIVIL PLANS FOR DETAILS, DIMENSIONS, ELEVATIONS, OPENINGS, ETC. NOTIFY ENGINEER OF ANY VARIANCE 1. BEFORE COMMENCING CONSTRUCTION.
- IN NO CASE SHALL STRUCTURAL ALTERATIONS OR WORK AFFECTING STRUCTURAL MEMBERS BE MADE, UNLESS APPROVED BY ENGINEER. 2
- 3 SIMILAR PORTIONS OF THE STRUCTURE SHALL HAVE SIMILAR DETAILING, UNLESS NOTED OTHERWISE.
- ALL WALL FORM TIES SHALL BE KNOCKED OFF FLUSH w/ THE FACE OF THE WALL AT INTERIOR AND EXTERIOR FACE OF WALLS. AT TIES BELOW THE FINISHED FLOOR AND/OR FINISHED GRADE PROVIDE A LAYER OF DAMPPROOFING PRODUCT OVER THE REMOVED TIE AREA. TYP.
- ALL FOOTINGS SHALL BEAR ON COMPACTED SOIL HAVING A MINIMUM BEARING CAPACITY EQUAL TO THE NET ALLOWABLE BEARING CAPACITY PER GEOTECHNICAL 5. REPORT
- THE ENGINEER SHALL BE NOTIFIED IF ACTUAL FIELD CONDITIONS DO NOT MEET BEARING REQUIREMENTS, OR IF QUESTIONABLE SOIL CONDITIONS ARE 6. DISCOVERED INCLUDING BUT NOT LIMITED TO PEAT AND OTHER HIGH ORGANIC SOILS OR EXPANSIVE CLAY.
- DO NOT USE EXCESSIVE COMPACTION EFFORTS ADJACENT TO TANK WALLS. SUCCESSIVE PASSES OF A COMPACTOR CAN RESULT IN WALL PRESSURE BUILD UP 7. **BEYOND THE DESIGN INTENT**
- DO NOT SCALE DRAWINGS. IF DIMENSIONS ARE IN QUESTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING CLARIFICATION FROM THE ENGINEER 8. BEFORE CONTINUING WITH CONSTRUCTION.
- REFER TO GEOTECHNICAL REPORT FOR REQUIREMENTS AND RECOMMENDATIONS FOR REMOVAL OF UNDESIRABLE SOILS, SITE SOIL, SUBGRADE PREPARATION, EXISTING SOIL INFORMATION, EXPECTED GROUNDWATER CONTROLS, AND BACKFILL RECOMMENDATIONS. STRUCTURAL BACKFILL, EXISTING SOIL BASE AND COMPACTION OF GRANULAR FILL LAYERS SHALL BE MONITORED BY A QUALIFIED GEOTECHNICAL ENGINEER. 9.
- PROVIDE MINIMUM 12" COMPACTED GRANULAR FILL LAYER BELOW ALL FOUNDATIONS, EXTEND 12" BEYOND SLAB. PROVIDE FILL DIRECTLY UNDER STRUCTURES AND WITHIN A 1H:1V ZONE OF INFLUENCE, UP TO, AROUND, AND ABOVE PLANNED FOUNDATION GRADES. SEE GEOTECHNICAL REPORT FOR MORE INFORMATION. 10. ADDITIONAL COMPACTED GRANULAR FILL MAY BE REQUIRED IN AREAS OF UNSUITABLE OR SOFT SOILS BELOW STRUCTURAL FOUNDATIONS OR FOOTINGS.

MSA 颜

@ MSA Pro

DESIGN STRESSES					
CAST-IN-PLACE CONCRETE					
WALLS AND FOOTINGSfc = 5000 PSI SLAB-ON-GRADEfc = 5000 PSI					
STEEL					
REINFORCINGfy = 60 KSI ASTM A615, GRADE 60					
ANCHORS					
ANCHOR BOLTS					
GEOTECHNICAL INFORMATION					
MAX NET ALLOWABLE SOIL BEARING PRESSUREq = 3000 PSF GEOTECHNICAL REPORT PREPARED BY:					

**CONCRETE MIX DESIGN** 

BRAUN INTERTEC CORPORATION

DATED: JUNE 30, 2022

28 DAY COMPRESSIVE STRESS	LISTED ABOVE
AIR CONTENT % (MIN-MAX)	
AGGREGATE, GRAVEL	

STEEL REINFORCING
N CLEAR COVER, UNO
ALLS & SLABS TOP & SIDES

M

۱۸/

**STRUCTURAL GENERAL NOTES & DESIGN STRESSES** 

PROJECT N 21720000

> SHEET S101

### CONSTRUCTION INSPECTION PLAN

PRIOR TO ANY SITEWORK, A PRECONSTRUCTION MEETING SHALL BE CONDUCTED BETWEEN THE OWNER, EXCAVATION CONTRACTOR TANK CONTRACTOR, CONSTRUCTION INSPECTOR/ENGINEER OF RECORD, SITE ENGINEER, AND THE NRCS/COUNTY LAND CONSERVATION DEPARTMENT

CONCRETE SUPPLIER TO PROVIDE ENGINEER WALL AND FLOOR MIX DESIGNS FOR APPROVAL, CONSISTENT WITH ACI 318 PRIOR TO POURING SLAB.

NRCS WISCONSIN CONSTRUCTION SPECIFICATION #4 - CONCRETE, SHALL BE USED FOR ALL PLACEMENT OF CONCRETE.

NRCS WISCONSIN CONSTRUCTION SPECIFICATION #004 - WS - EMBEDDED OR EXPANSIVE WATERSTOP SHALL BE USED FOR ALL WATERSTOP INSTALLATION

CONSTRUCTION INSPECTOR MUST BE COMPETENT IN INTERPRETING CONSTRUCTION DOCUMENTS, FAMILIAR WITH TYPE OF CONSTRUCTION, INDEPENDENT, AND NOT A DIRECT EMPLOYEE OF CONTRACTOR

CONSTRUCTION INSPECTOR WILL BE RESPONSIBLE FOR AS-BUILT DOCUMENTATION, CONSTRUCTION INSPECTION LOG, AND PHOTOGRAPHS

CONSTRUCTION INSPECTOR TO INSPECT REBAR SIZE, LOCATION, SPACING, AND WATERSTOP LOCATIONS IN BASE SLAB PRIOR TO CONCRETE POUR. SLAB IS TO BE POURED AS INDICATED ON PLAN TO COMPLETE THE TANK. INSPECTED ITEMS SHALL BE AS FOLLOWS:

- PROVIDE CONTINUOUS INSPECTION OF CONCRETE PLACEMENT AROUND THE WATERSTOP TO ENSURE CONSOLIDATION
- NUMBER AND SPACING OF BASE SLAB REINFORCING
- SPACING OF WALL DOWELS
- BASE SLAB WATERSTOP JOINT
- BASE SLAB WATERSTOPS, IF REQUIRED

CONSTRUCTION INSPECTOR TO INSPECT REBAR SIZE, LOCATION, SPACING, AND WATERSTOP LOCATION IN EACH WALL SECTION PRIOR TO CONCRETE POUR. WALL IS TO BE POURED IN 100 FOOT LONG MAXIMUM SECTIONS TO COMPLETE THE TANK. INSPECTED ITEMS SHALL BE AS FOLLOWS:

- CONCRETE PLACEMENT ADJACENT TO ALL WATERSTOP
- SPACING OF WALL VERTICAL AND HORIZONTAL REINFORCING
- WALL WATERSTOP AT JOINT AFTER WELDING TO FOOTING WATERSTOP
- FORM TIE HOLE PLUGS AT INSIDE FACE OF WALL

GROUTED FORM TIE HOLES AT OUTSIDE FACE OF WALL

### TESTING FOR CONCRETE GREATER THAN 4,000 PSI:

ALL CONCRETE WITH REQUIRED COMPRESSIVE STRENGTH ABOVE 4,000 PSI MUST BE TESTED. CONTRACTOR SHALL ENGAGE A QUALIFIED INDEPENDENT TESTING AND INSPECTING AGENCY TO SAMPLE MATERIALS, PERFORM TESTS, AND SUBMIT TEST REPORTS DURING CONCRETE PLACEMENT. CAST AND LABORATORY CURE ONE SET OF FOUR STANDARD CYLINDERS FOR EACH COMPOSITE SAMPLE FOR EACH DAY'S POUR OF EACH CONCRETE MIX. PROVIDE FOUR CYLINDERS FOR EACH 200 CU. YD. OR FRACTION THEREOF. PERFORM TESTS ACCORDING TO ACI 318 - INSPECTION AND TESTING. TEST ONE SPECIMEN AT 7 DAYS AND TWO SPECIMENS AT 28 DAYS.

#### SITEWORK SPECIFICATION

SITE ENGINEER TO VERIFY SUBGRADE WITH COMPACTED SUBBASE IS CAPABLE OF SUPPORTING A BEARING PRESSURE OF 3000 PSF & A SUBGRADE MODULUS OF 200 PCI. COMPACTED GRANULAR SUBBASE SHALL BE MINIMUM 6" THICK OF CLEAN SAND OR 3/4" CRUSHED STONE WITH FINES. PROVIDE ADDITIONAL COMPACTED GRANULAR SUBBASE UP TO 10" THICK SHOULD SUBGRADE MODULUS RANGE BETWEEN 100 TO 200 PCI.

#### BACKFILLING

ONCE THE CONCRETE IS PROPERLY CURED, BACKFILL CAN BE PLACED AROUND THE TANK. AVOID BACKFILL CONTAINING LARGE ROCKS, HARD OR FROZEN SOIL LUMPS, OR CONSTRUCTION DEBRIS.

BACKFILL MATERIAL MUST BE PLACED FROM THE HEEL OF THE FOOTING AT A 45° ANGLE AWAY FROM THE WALL UNTIL SURFACE ELEVATION IS ENCOUNTERED. BACKFILL SHALL BE COMPACTED TO AT LEAST 95 PERCENT MAXIMUM DRY DENSITY PER MODIFIED PROCTOR

GRANULAR BACKFILL MATERIAL INCLUDES GW, GP, GM, GC, SW, SP, AND SM SOILS. CLAY/SILT BACKFILL MATERIAL INCLUDES SM-SC, SC, ML, CL-ML, AND CL SOILS. MH AND CH SOILS ARE NOT PERMITTED TO BE USED AS BACKFILL MATERIAL. IF PROPOSED TO BE USED AS BACKFILL A SPECIAL DESIGN MUST BE USED.

#### ADJACENT TO TANK

WITHIN 2 FEET OF TANK, EARTHFILL SHALL BE PLACED IN 4-INCH LIFTS (PRIOR TO COMPACTION) IN A MANNER ADEQUATE TO PF DAMAGE TO THE STRUCTURE AND TO ALLOW THE STRUCTURE OR PIPE TO GRADUALLY AND UNIFORMLY ASSUME THE BACKFILL LOADS. COMPACTION SHALL BE ACCOMPLISHED BY MEANS OF MANUALLY DIRECTED POWER TAMPERS OR PLATE VIBRATORS OR HAND TAMPING UNLESS OTHERWISE SPECIFIED. HEAVY EQUIPMENT SHALL NOT BE OPERATED WITHIN 2 FEET OF TANK. COMPACTION BY MEANS OF DROP WEIGHTS OPERATING FROM A CRANE OR HOIST OF ANY TYPE WILL NOT BE PERMITTED.

THE TANK SITE SHALL BE GRADED TO PROVIDE DRAINAGE ACCORDING TO SITE ENGINEER'S GRADING PLAN.

## SOIL BORING REQUIREMENT

1/11/2023 DRAWN BY: BLS

DESIGNED BY: MLB

CHECKED BY: SHG

JECT DATE:

THE OWNER SHALL HIRE GEOTECHNICAL FIRM TO CONDUCT SUBSURFACE INVESTIGATION WHEN

BUILDING MORE THAN 20% OF THE TANK FLOOR AREA ON FILL DUE TO TANK BEING LOCATED ON SIDE OF HILL SITE SOILS ARE INCAPABLE OF PROVIDING THE REQUIRED MINIMUM ALLOWABLE BEARING PRESSURE

BORINGS SHALL BE TAKEN TO ESTABLISH AMOUNT OF ANTICIPATED DIFFERENTIAL SETTLEMENT THAT MAY OCCUR BETWEEN THE FILL AND NON-FILL AREAS OF THE STRUCTURE. IF DIFFERENTIAL SETTLEMENT IS AN ISSUE, PRE-LOADING OF FILL AREA WITH APPROPRIATE OVERBURDEN MAY BE REQUIRED TO MINIMIZE THE FUTURE MOVEMENT. GEOTECHNICAL INVESTIGATION SHALL ALSO ESTABLISH AN ALLOWABLE SOIL BEARING PRESSURE FOR WALL FOUNDATIONS.

BORINGS ARE NOT REQUIRED WHEN ENTIRE TANK FOOTPRINT IS BEING UNIFORMLY RAISED ON FILL TO CREATE NECESSARY SEPARATION FROM GROUNDWATER OR BEDROCK, AND WHEN EXISTING SITE SOILS ARE CAPABLE OF PROVIDING THE REQUIRED MINIMUM ALLOWABLE BEARING PRESSURE

### ESTABLISHING AND MAINTAINING VEGETATION

NRCS CODE 342-CRITICAL AREA PLANTING SHALL BE DONE BY OTHERS UNDER DIRECTION OF SITE ENGINEER

NRCS WISCONSIN CONSTRUCTION SPECIFICATION #4 - CONCRETE, SHALL BE USED FOR ALL PLACEMENT OF CONCRETE.

NRCS WISCONSIN CONSTRUCTION SPECIFICATION #004 - WS - EMBEDDED OR EXPANSIVE WATERSTOP SHALL BE USED FOR ALL WATERSTOP INSTALLATION

#### OPERATION AND MAINTENANCE PLAN

FENCING, GUARDRAILS, AND OTHER SAFETY FEATURES SHOWN ON CONSTRUCTION DOCUMENTS SHALL BE INSPECTED & MAINTAINED TO ENSURE SAFE OPERATION OF WASTE STORAGE FACILITY AND PREVENT ACCESS BY HUMANS OR LIVESTOCK.

SLAB DESIGN ALLOWS FOR A 23,200 LBS MAXIMUM VEHICLE AXLE LOAD FOR 5" SLAB.

#### OTHER REQUIREMENTS

- FOLLOWING EMPTYING OF THE FACILITY, INSPECT THE CONCRETE WALLS AND SLAB FOR SEPARATION OR CRACKING AND REPAIR THEM AS NEEDED.
- INSPECT PUMPS, PIPES, AND VALVES TWICE YEARLY TO ENSURE THEY ARE

CONTINGENCY PLAN

# EMERGENCY RESPONSE PLAN

PERSONNEL

MANAGEMENT PLAN.

PROVIDE TEMPORARY EARTHEN BARRIERS TO CONTAIN LIQUID AND TO STOP LIQUID FROM ENTERING NEARBY WATERWAYS OR STORMWATER SYSTEM. RETURN SPILLED MANURE TO WASTE STORAGE TANK OR APPLY TO LAND ACCORDING TO 590 NUTRIENT MANAGEMENT PLAN.

DO REGULAR INSPECTIONS OF PIPES, PUMPS, AND VALVES TO ENSURE PROPER OPERATION AT POTENTIAL SPILL

CONFINED SPACES WHERE HUMAN ENTRY MAY OCCUR SHALL BE DESIGNED AND OPERATED IN COMPLIANCE WITH THE PROVISIONS CONTAINED IN ASABE EP470. MANURE STORAGE SAFETY.

POST WARNING SIGNS ON OR NEXT TO ALL CONFINED SPACES. THE SIGNS SHOULD BE STURDY, WEATHERPROOF, AND DISPLAY SUCH WORDING AS, "DANGER! CONFINED SPACE, DO NOT ENTER" REGULARLY INSPECT ALL WARNING SIGNS TO MAKE SURE THEY ARE CLEAN, READABLE, AND HAVE NOT BEEN TAMPERED WITH

BE SURE THAT ALL OPENINGS TO CONFINED SPACES ARE APPROPRIATELY COVERED OR BLOCKED OFF. OPENINGS SHOULD BE COVERED WITH SUBSTANTIAL METAL GRILL COVERS. THESE PROVIDE NATURAL VENTILATION, AND HELP PREVENT ACCIDENTAL FALLS OR UNAUTHORIZED ENTRY.

ENTRY.

IN TROUBLE IN A CONFINED SPACE

ALL MECHANICAL AND ELECTRICAL EQUIPMENT MUST BE LOCKED OUT.

USE THE "BUDDY SYSTEM" AND WEAR A LIFELINE, SUFFICIENT EQUIPMENT AND MANPOWER MUST BE AVAILABLE. A THIRD PERSON SHOULD BE ON HAND TO SUMMON ASSISTANCE IF NEEDED.

IN THE EVENT UN-INTENTIONAL FLOOR CRACKING OR CRACK MIGRATIONS OCCUR REPAIR THE CRACKS WITH A SIMPSON ETI-LV EPOXY ADHESIVE. THE REPAIR INVOLVES INJECTING LOW-VISCOSITY EPOXY INTO THE CRACKS TO MAKE THEM WATERPROOF. USE "GRAVITY-FEED APPLICATION" WHICH MEANS DISPENSING THE OIL-LIKE VISCOSITY EPOXY ALONG THE CRACK TO FILL IT WITHOUT PRESSURE. IN THE EVENT OF NARROW CRACKS, SIMPSON RECOMMENDS USING TWO BEADS OF CAULK ALONG EACH SIDE OF THE CRACK APPROXIMATELY 1/8" FROM THE EDGE OF THE CRACK TO WORK AS A RESERVOIR FOR THE EPOXY. ALTERNATIVELY, THE INSTALLER MAY ROUT THE CRACK TO FORM A V-GROOVE. WITH ROUTING. IT IS REQUIRED TO CLEAN THE CRACK WITH COMPRESSED AIR AFTERWARDS AS ROUTING CAN IMPACT DUST AND DEBRIS INTO THE CRACK AND PREVENT PROPER FLOW OF THE EPOXY.

## OWNER AGREEMENT TO O/M PLAN

SIGNED

2022 EQIP WASTE STORAGE FACILITY 1230 SOUTH BOULEVARD, BARABOO WI 53913 (608) 356-2771 www.msa-ps.com **BROOKS FARMS DAIRY, LLC** WAUPACA COUNTY, WI

REVENT			

ENGINEERING | ARCHITECTURE | SURVEYIN FUNDING | PLANNING | ENVIRONMENTAL

@ MSA Prof

FUNCTIONAL AND NOT A SAFETY HAZARD.

BEGIN PLANNED CONTINGENCY UTILIZATION OF MANURE BY APPLYING ON FIELDS AT RATES ACCORDING TO 590 NUTRIENT MANAGEMENT PLAN.

HAVE NAME AND PHONE NUMBER OF A LICENSED SEPTIC WASTE HAULER READILY AVAILABLE TO FARM

CALL LICENSED SEPTIC TANK WASTE HAULER TO VACUUM SPILLED MANURE INTO VACUUM TANK AND DEPOSIT BACK INTO WASTE STORAGE TANK OR APPLY TO LAND ACCORDING TO 590 NUTRIENT

ASSESS THE EXTENT OF THE SPILL AND NOTIFY THE DNR.

## CONFINED SPACE ENTRY INTO MANURE TRANSFER SYSTEM

IF EMPLOYEES ARE NOT REQUIRED TO ENTER A CONFINED SPACE, LOCK THE OPENING TO PREVENT

OBEY ALL WARNING SIGNS ON AND AROUND CONFINED SPACES

AVOID GOING NEAR CONFINED SPACES WHILE SMOKING OR USING ELECTRICAL EQUIPMENT

NOTIFY SOMEONE WHO HAS BEEN TRAINED IN CONFINED RESCUE OPERATIONS IF THEY SPOT ANYONE

CONFINED SPACES CAN BE DEADLY. IF THE AIR IN THE SPACE IS NOT TESTED BEFORE ENTRY, YOU COULD BE OVERCOME BY FUMES AND PASS OUT OR DIE DUE TO LACK OF OXYGEN, TOXIC GASES, OR AN INABILITY TO ESCAPE QUICKLY ENOUGH. MULTIPLE DEATHS OFTEN OCCUR WHEN ONE PERSON ENTERS THE SPACE, IS OVERCOME, AND OTHERS TRY UNSUCCESSFULLY TO SAVE THE FIRST PERSON.

FOLLOWING ARE THE BASIC GUIDELINES FOR CONFINED SPACE ENTRY

TEST THE ATMOSPHERE FOR OXYGEN, AND FOR LEVELS OF TOXIC AND EXPLOSIVE GASES.

IF A DANGEROUS ATMOSPHERE EXISTS, YOU MUST WEAR A SELF-CONTAINED BREATHING APPARATUS. VENTILATE THE AREA AS THOROUGHLY AS POSSIBLE

ESTABLISH HOW YOU WILL BE COMMUNICATING BEFORE ENTERING THE CONFINED SPACE. THE MEANING OF VERBAL SIGNALS, HAND GESTURES, OR TUGGING LINE SIGNALS MUST BE UNDERSTOOD BY THE PEOPLE ON THE OUTSIDE

NEVER RE-ENTER A CONFINED SPACE WITHOUT RE-TESTING AND VENTING THE AREA.

EMERGENCY SLAB CRACK REPAIR PLAN

DATE

STRUCTURAL CONSTRUCTION NOTES

ROJECT 21720000

> SHEET S102

### CD CODES AND DOCUMENTS

CD-1 ALL CONSTRUCTION SHALL BE PERFORMED IN CONFORMANCE WITH THE BUILDING AND DESIGN CODES REFERENCED WITHIN THESE DOCUMENTS. THE PROJECT DOCUMENTS REFER TO THE FOLLOWING CODES AND STANDARDS, UNLESS OTHERWISE NOTED:

BUILDING CODE INTERNATIONAL BUILDING CODE 2015 ASCE 7-10 MINIMUM DESIGN LOADS FOR BUILDINGS AND OTHER STRUCTURES

STRUCTURAL CONCRETE: NRCS CODE 313 "WASTE STORAGE FACILITY" OCTOBER 2017R NRCS CODE 522 "POND SEALING OR LINING, CONCRETE" JUNE 2021 NRCS CODE 634 "WASTE TRANSFER" AUGUST 2016 BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, ACI 318-14 GUIDE TO DESIGN OF SLABS-ON-GRADE, ACI 360R PCA CONCRETE FLOORS ON GROUND (2ND EDITION) CRSI MANUAL OF STANDARD PRACTICE NRCS CODE #4 "CONCRETE" DECEMBER 2017 NRCS CODE #004 - WS "EMBEDDED OR EXPANSIVE WATERSTOP" MAY 2018

CD-2 "DRAWINGS" MEANS THE LATEST STRUCTURAL DESIGN DRAWINGS, UNLESS OTHERWISE NOTED. "SPECIFICATIONS" MEANS THE LATEST PROJECT SPECIFICATIONS, UNLESS OTHERWISE NOTED

CD-3 THE SPECIFICATIONS ARE AN INTEGRAL PART OF THE CONTRACT DOCUMENTS AND SHALL BE USED IN CONJUNCTION WITH THE STRUCTURAL DRAWINGS. IN CASES, IF ANY, WHERE REQUIREMENTS INDICATED ON THE STRUCTURAL DRAWINGS DIFFER FROM THE SPECIFICATIONS, NOTIFY THE STRUCTURAL ENGINEER FOR RESOLUTION.

CD-4 ALL DETAILS, SECTIONS AND NOTES ON THE DRAWINGS ARE INTENDED TO BE TYPICAL WHERE CONDITIONS ARE SIMILAR TO THOSE INDICATED BY DETAIL OR DETAIL TITLE OR NOTE.

CD-5 ASSUME EQUAL SPACING IF NOT INDICATED ON DRAWINGS

CD-6 USE ONLY DIMENSIONS INDICATED ON THE DRAWINGS. DO NOT SCALE DRAWINGS OR USE ANY DIMENSIONS TAKEN FROM ELECTRONIC DRAWING FILES

### CC CONTRACTOR RESPONSIBILITIES AND COORDINATION

CC-1 THE CONTRACTOR SHALL FURNISH ALL LABOR AND MATERIALS FOR SUCCESSFUL COMPLETION OF THIS PROJECT

CC-2 THE STRUCTURAL DRAWINGS AND NOTES REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION, UNLESS OTHERWISE NOTED. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE MEANS, METHOD, TECHNIQUES, SEQUENCES, AND OPERATION OF CONSTRUCTION AND SAFETY PRECAUTIONS AND PROGRAMS INCIDENTAL THERETO.

CC-3 THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE DESIGN, INSTALLATION, AND REMOVAL OF ALL TEMPORARY BRACING AND CONSTRUCTION SUPPORTS, FOR NEW AND EXISTING STRUCTURES, AS NECESSARY TO COMPLETE THE PROJECT. NO PORTION OF THE PROJECT, WHILE UNDER CONSTRUCTION, IS INTENDED TO BE STABLE IN THE ABSENCE OF THE CONTRACTOR'S TEMPORARY BRACES AND SUPPORTS. CONTRACTOR SHALL RETAIN A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF WISCONSIN TO DESIGN ALL TEMPORARY BRACING AND CONSTRUCTION SUPPORTS.

CC-4 THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND ELEVATIONS, NEW AND EXISTING, BY MEASUREMENTS AND SURVEYS AT THE JOB SITE, PRIOR TO SUBMITTAL OF SHOP DRAWINGS. THE CONTRACTOR SHALL TAKE ANY AND ALL OTHER MEASUREMENTS NECESSARY TO VERIFY CONFORMANCE WITH THE DRAWINGS AND TO PERFORM THE WORK PROPERLY. THE CONTRACTOR SHALL VISIT SITE TO TAKE INTO ACCOUNT ALL EXISTING CONDITIONS AS THEY MAY AFFECT THE WORK, AND INCLUDE IN THE BID WORK THAT IS REQUIRED TO COMPLETE THE WORK.

CC-5 IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO COORDINATE THE STRUCTURAL WORK WITH THE ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS, AS WELL AS ANY OTHER APPLICABLE TRADES. IN CASE OF CONFLICT BETWEEN THE STRUCTURAL WORK AND DRAWINGS RELATED TO OTHER TRADES, THE CONTRACTOR SHALL MAKE ALLOWANCES IN HIS BID FOR THE MORE SEVERE REQUIREMENT. CONFLICTS BETWEEN THE STRUCTURAL WORK AND THE DRAWINGS OF OTHER TRADES SHALL NOT BE REASON FOR ANY EXTRA COST OR DELAY IN THE EXECUTION OF THE WORK

CC-6 ALL FIELD WORK SHALL BE COORDINATED AND CONTINUOUSLY SUPERVISED BY THE CONTRACTOR.

CC-7 MATERIALS AND EQUIPMENT SHALL BE STORED AND TRANSPORTED IN A MANNER SO AS NOT TO EXCEED THE ALLOWABLE LOADING INDICATED IN THE DRAWINGS.

CC-8 THE CONTRACTOR SHALL NOTIFY THE STRUCTURAL ENGINEER OF ANY DISCREPANCIES BETWEEN THE STRUCTURAL DRAWINGS AND SPECIFICATIONS AND ANY OTHER DOCUMENTS OR EXISTING CONDITIONS FOR RESOLUTION PRIOR TO PROCEEDING WITH THE WORK. DO NOT ASSUME THAT EITHER THE DRAWINGS OR SPECIFICATIONS TAKE PRECEDENCE.

CC-9 THE CONTRACTOR SHALL VERIFY WITH THE GEOTECHNICAL ENGINEER THAT THE PROPOSED CONSTRUCTION PROCEDURES AND SEQUENCES FOLLOW THE RECOMMENDATIONS WITHIN THE GEOTECHNICAL REPORT AND SOIL BORINGS.

CC-10 THE CONTRACTOR SHALL MAKE NO DEVIATION FROM THE DESIGN DRAWINGS WITHOUT WRITTEN APPROVAL FROM THE STRUCTURAL ENGINEER.

1/11/2023 DRAWN BY:

BLS

DESIGNED BY: MLB

CHECKED BY: SHG

JECT DATE

CC-11 SEE CIVIL DRAWINGS FOR ADDITIONAL INFORMATION RELATING TO THE COORDINATION OF STRUCTURAL COMPONENTS INCLUDING, BUT NOT LIMITED TO: CIVII ·

SITE PREPARATION

BACK-FILLING MATERIALS AND REQUIREMENTS PAVING AND SITE ELEMENTS OUTSIDE OF STRUCTURAL ENVELOPE

CC-12 PRINCIPAL OPENING SIZES AND LOCATIONS ARE INDICATED ON THE DRAWINGS. ADDITIONAL OPENINGS, BLOCK OUTS, AND SLEEVES MAY BE REQUIRED BY OTHER DISCIPLINES AND SHALL BE CONSTRUCTED USING THE CRITERIA INDICATED IN THE STRUCTURAL DOCUMENTS. CONTRACTOR TO SUBMIT PROPOSED OPENING LOCATIONS AND METHOD OF CONSTRUCTION FOR OPENINGS NOT SHOWN ON STRUCTURAL DOCUMENTS TO THE STRUCTURAL ENGINEER FOR APPROVAL PRIOR TO CONSTRUCTION.

CC-13 BY SUBMITTING A BID, THE BIDDER AGREES AND WARRANTS THAT THE DRAWINGS HAVE BEEN EXAMINED AND FOUND THAT THEY ARE ADEQUATE FOR PROPER COMPLETION OF THE PROJECT.

### SU SUBMITTALS

SU-1 THE CONTRACTOR IS TO REVIEW EACH SUBMITTAL PRIOR TO FORWARDING TO STRUCTURAL ENGINEER. THE CONTRACTOR IS TO STAMP EACH SUBMITTAL VERIFYING THAT THE FOLLOWING IS ADDRESSED: 1.THE SHOP DRAWING IS REQUESTED.

2.THE SHOP DRAWING IS BASED ON THE LATEST DESIGN

3.THE STRUCTURAL ENGINEER'S COMMENTS FROM ANY PREVIOUS SUBMITTALS ARE ADDRESSED 4.THE WORK IS COORDINATED AMONG ALL CONSTRUCTION TRADES.

- 5.REVISIONS FROM PREVIOUS SUBMITTALS ARE CLEARLY MARKED BY CIRCLING OR CLOUDING.
- 6.FIELD DIMENSIONS THAT DIFFER FROM THE DRAWINGS ARE NOTED. 7.SUBMITTAL IS COMPLETE.

THE STRUCTURAL ENGINEER MAY RETURN, WITHOUT COMMENT, SUBMITTALS THAT THE CONTRACTOR HAS NOT STAMPED OR WHICH DO NOT MEET THE ABOVE REQUIREMENTS. THE STRUCTURAL ENGINEER'S REVIEW OF SUBMITTALS SHALL BE FOR GENERAL CONFORMANCE WITH THE DESIGN INTENT. NO WORK SHALL BE STARTED WITHOUT SUCH REVIEW.

SU-2 FOR COMPONENTS THAT REQUIRE ENGINEERING BY THE SUPPLIER, PROVIDE A NOTE ON EACH SHOP DRAWING WRITTEN AND SIGNED BY THE SUPPLIER'S ENGINEER, INDICATING THAT THE SHOP DRAWING IS IN CONFORMANCE WITH THE CALCULATIONS OF THE SUPPLIER'S ENGINEER.

SU-3 THE FOLLOWING ITEMS REQUIRE SUBMITTALS FOR STRUCTURAL REVIEW S CONCRETE REINFORCING LAYOUT S CONCRETE MIX DESIGNS

S CONCRETE CONSTRUCTION JOINT LAYOUT S CONCRETE FORMWORK

S = SHOP DRAWINGS RECOMMENDED

### TI TESTING AND INSPECTION

TI-1 THE FOLLOWING STRUCTURAL ITEMS REQUIRE TESTING AND/OR INSPECTIONS AS REQUIRED BY THE GOVERNING BUILDING CODES LIST IN CODES AND DOCUMENTS AND AS OUTLINED IN THE SPECIFICATIONS: CONCRETE REINFORCEMENT

- EXPANSION AND ADHESIVE ANCHORS
- FOUNDATIONS
- CAST IN PLACE CONCRETE

TI -2 SEE SHEET S102 FOR ADDITIONAL TESTING AND INSPECTION INFORMATION

## FO FOUNDATIONS

FO-2 THE FOUNDATION DESIGN IS BASED ON THE GEOTECHNICAL INVESTIGATION REPORT BY BRAUN INTERTEC CORPORATION, DATED: JUNE 30, 2022.

FO-3 THE CONTRACTOR SHALL VERIFY WITH THE GEOTECHNICAL ENGINEER THAT THE FOLLOWING IS IN CONFORMANCE WITH THE RECOMMENDATIONS OUTLINED IN THE GEOTECHNICAL REPORT: A. THE BEARING STRATUM AT EACH FOUNDATION IS AS ASSUMED IN THE REPORT. THE ALLOWABLE BEARING CAPACITIES MEET OR EXCEED THE RECOMMENDED VALUES. THE ENGINEERED FILL IS INSTALLED PER THE RECOMMENDATIONS. THE INSTALLATION OF THE FOUNDATIONS IS AS ASSUMED IN THE REPORT

FO-5 THE CONTRACTOR SHALL USE CARE IN GRADING AND EXCAVATION NOT TO DAMAGE EXISTING ITEMS TO REMAIN. DAMAGE TO THE EXISTING ITEMS BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE

FO-6 EXCAVATE, BRACE, AND BACKFILL SLAB AT GRADE PITS FOLLOWING RECOMMENDATIONS FROM GEOTECHNICAL REPORT, PRIOR TO CONSTRUCTION OF NEW FOOTINGS.

FO-7 SLABS ON GRADE HAVE NOT BEEN DESIGNED FOR UPLIFT.

RE REINFORCEMENT PROPERTIES

RE-2 DETAIL REINFORCEMENT BASED ON THE PROJECT REQUIREMENTS, ACI-318, ACI-315, ACI-117, AND CRSI MANUAL OF STANDARD PRACTICE.

RE-3 ALL LAP SPLICES ARE TO BE ACI STANDARD CLASS B TENSION LAP SPLICES. WHERE BARS OF DIFFERENT SIZES LAP, PROVIDE LAP SPLICE LENGTH FOR LARGER BAR.

RE-4 WHERE A 90° HOOK IS GRAPHICALLY INDICATED, PROVIDE ACI STANDARD 90° HOOK. WHERE A 135° HOOK IS GRAPHICALLY INDICATED, PROVIDE ACI STANDARD 135° HOOK. WHERE A 180° HOOK IS GRAPHICALLY INDICATED, PROVIDE ACI STANDARD 180° HOOK

RE-6 FOR BARS INDICATED IN GROUPS, PROVIDE BARS OF EACH GROUP AT EQUAL SPACING, UNLESS OTHERWISE NOTED

RE-7 WHERE DOWELS ARE INDICATED BUT NOT SIZED, PROVIDE DOWELS THAT MATCH SIZE AND LOCATION OF MAIN REINFORCEMENT AND LAP SPLICE WITH THE MAIN REINFORCEMENT.

UNLESS OTHERWISE NOTED:

RE-10 NO CONSTRUCTION SHALL BE MADE WITHOUT REINFORCEMENT

ANTI-CORROSIVE ZINC RICH PRIMER

RE-13 STORE MATERIAL IN ACCORDANCE WITH ACI 304R.

G   PLANNING   ENVIRONMENTAL	2022 EC
BOULEVARD, BARABOO WI 53913 356-2771 www.msa-ps.com	
© MSA Professional Services, Inc.	

01	R		ENGINEER FUNDING
	<b>W</b>	MSA	1230 SOUTH (608)

EQ-1 THE OWNER SHALL RETAIN THE SERVICES OF A QUALIFIED GEOTECHNICAL ENGINEERING FIRM FOR TESTING AND OBSERVATION DURING EXCAVATION, BACKFILL, AND FOUNDATION CONSTRUCTION PHASES OF THIS PROJECT TO VERIFY THAT DESIGN REQUIREMENTS ARE MET

FO-4 PLACE FOOTINGS AND SLAB ON GRADE ON UNDISTURBED, NATURAL SUBGRADE, AS VERIFIED BY A QUALIFIED GEOTECHNICAL ENGINEER RETAINED FOR THE PROJECT. IF SUBGRADE IS DEEMED UNSUITABLE, EXTEND EXCAVATION TO SUITABLE, UNDISTURBED NATURAL SUBGRADE AND RAISE GRADE USING COMPACTED ENGINEERED FILL OR PLAIN CONCRETE, AS DETERMINED AND INSPECTED BY THE QUALIFIED GEOTECHNICAL ENGINEER.

FILL OR BACKFILL MATERIAL CAN CONSIST OF WELL-GRADED GRANULAR FILI APPROVED BY A SOILS ENGINEER. COHESIVE SOIL AND SILTY/CLAYEY GRANULAR MATERIAL MAY BE ACCEPTABLE ABOVE SUBGRADES THAT HAVE BEEN STABILIZED WITH GRANULAR MATERIALS. FILL MUST BE FREE OF UNSUITABLE SOIL, FROZEN MATERIAL, RUBBLE ORGANICS, DEGRADABLE MATERIAL, CHEMICAL CONTAMINANTS AND STONES THAT WOULD INTERFERE WITH COMPACTION OR COMPACTION TESTING. COMPACT FILL TO AT LEAST 95% OF ITS MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D696.

RE-1 REINFORCEMENT SHALL CONFORM TO THE FOLLOWING STANDARDS AND MATERIAL

DEFORMED BARS: ASTM A615 GRADE 60

RE-5 PROVIDE ACI STANDARD FULL TENSION WELDED WIRE LAP SPLICE FOR WELDED WIRE

RE-8 WHERE CONCRETE ELEMENTS INTERSECT WALLS, PROVIDE DOWELS TO EXTEND CONTINUOUS WALL REINFORCEMENT. AT THE INTERSECTION OF CONCRETE FOOTINGS OR WALLS, PROVIDE CORNER BARS THE SAME SIZE AND SPACING AS CONTINOUS OR HORIZONTAL REINFORCING, RESPECTIVELY, UNLESS NOTED OTHERWISE.

RE-9 REINFORCEMENT SHALL HAVE THE FOLLOWING CONCRETE PROTECTION (CLEAR COVER),

UNFORMED SURFACES IN CONTACT WITH SOIL OR WATER, OR EXPOSED TO WEATHER: 3" FORMED SURFACES IN CONTACT WITH SOIL OR WATER. OR EXPOSED TO WEATHER: 2"

RE-12 FOR CONCRETE THAT IS FIELD CUT, EXPOSED REINFORCING SHALL BE COATED WITH AN

ROJECT 21720000

STRUCTURAL SPECIFICATION SHEET

SHEET S103
### CM CONCRETE MATERIAL PROPERTIES

CM-1 PREPARE DESIGN MIXES FOR EACH TYPE AND STRENGTH OF CONCRETE BY EITHER LABORATORY TRIAL BATCH OR FIELD EXPERIENCE METHODS AS SPECIFIED IN ACI 301.

- A. SLUMP SHALL BE 4" MAXIMUM, 2" MINIMUM FOR WALLS AND FOOTINGS AND 5" MAXIMUM, 3" MINIMUM FOR SLABS-ON-GRADE.
- B. LIMIT THE USE OF FLY ASH TO 15% OF THE CEMENT CONTENT. (PERCENTAGE COULD BE INCREASED TO 20% FOR TYPE C. FLY ASH LOWERS THE HEAT OF HYDRATION SO USE CAUTION IN WINTER MONTHS.)
- C. CONTRACTOR SHALL EXERCISE CARE IN SELECTION OF MIX DESIGN AND CURING METHODS TO MINIMIZE THE DIFFERENTIAL MOISTURE LOSSES THAT MAY RESULT IN CURLING OF CONCRETE SLABS PLACED OVER POLYETHYLENE.
- D. COMPRESSIVE STRENGTH: STRENGTH REQUIREMENTS AT 28 DAYS AND THE LOCATIONS OF EACH TYPE OF CONCRETE REQUIRED FOR THIS PROJECT SHALL BE AS NOTED IN DESIGN DATA.

CM-2 PROVIDE NORMAL WEIGHT CONCRETE WITH MINIMUM CURED DENSITY OF 145 PCF, AND AGGREGATE CONFORMING TO ASTM C33, UNLESS OTHERWISE NOTED.

CM-3 THE USE OF CALCIUM CHLORIDE AND OTHER CHLORIDE-CONTAINING AGENTS IS PROHIBITED. THE USE OF RECYCLED CONCRETE IS PROHIBITED. PLACEMENT WITHIN AND CONTACT BETWEEN ALUMINUM ITEMS, INCLUDING ALUMINUM CONDUIT, AND CONCRETE IS PROHIBITED.

CM-4 CONCRETE EXPOSED TO WEATHER SHALL BE AIR-ENTRAINED, RESULTING IN A TOTAL AIR CONTENT OF 6% +/- 1%, A MAXIMUM SLUMP OF 4 INCHES, WITH A W/C RATIO OF 0.45.

### CP CAST IN PLACE CONCRETE

DJECT DATE

1/11/2023 DRAWN BY: BLS

DESIGNED BY: MLB

CHECKED BY: SHG

CP-1 CONCRETE WORK SHALL CONFORM TO ALL REQUIREMENTS OF ACI 301, LATEST EDITION, SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS, EXCEPT AS MODIFIED BY SUPPLEMENTAL REQUIREMENTS CONTAINED IN THE FOLLOWING NOTES.

CP-2 UNLESS OTHERWISE DETAILED OR NOTED, REINFORCING SHALL BE IN ACCORDANCE WITH "THE ACI DETAILING MANUAL, SP-66."

CP-3 ALL CONCRETE TESTING SHALL BE PERFORMED UNDER THE DIRECT SUPERVISION OF A QUALIFIED ENGINEER WHO IS LICENSED TO PRACTICE IN THE STATE OF WISCONSIN. THE TESTING AGENCY SHALL MEET REQUIREMENTS CONTAINED IN ASTM E329.

CP-4 DESIGN, ERECT, SUPPORT, BRACE AND MAINTAIN FORMWORK TO SUPPORT VERTICAL AND LATERAL LOADS THAT WILL BE IMPOSED BY CONCRETE AND CONSTRUCTION ACTIVITIES. CONSTRUCT FORMWORK SO CONCRETE MEMBERS AND STRUCTURES ARE OF CORRECT SIZE, SHAPE, ALIGNMENT, ELEVATIONS AND POSITION.

CP-5 PROVIDE SUPPORTS FOR REINFORCING, INCLUDING BOLSTERS, CHAIRS, SPACERS AND OTHER DEVICES FOR SPACING, SUPPORTING AND FASTENING REINFORCING BARS AND WELDED WIRE FABRIC IN PLACE. USE WIRE BAR TYPE SUPPORTS COMPLYING WITH CONCRETE REINFORCING STEEL INSTITUTE (CRSI) RECOMMENDATIONS, UNLESS OTHERWISE APPROVED.

CP-6 COLD WEATHER PLACING: PROTECT CONCRETE WORK FROM PHYSICAL DAMAGE OR REDUCED STRENGTH, WHICH COULD BE CAUSED BY FROST, FREEZING ACTIONS OR LOW TEMPERATURES, IN COMPLIANCE WITH ACI 306. DO NOT USE CALCIUM CHLORIDE, SALT AND OTHER MATERIALS CONTAINING ANTIFREEZE AGENTS.

CP-7 HOT WEATHER PLACING: WHEN HOT WEATHER CONDITIONS EXIST THAT WOULD SERIOUSLY IMPAIR QUALITY AND STRENGTH OF CONCRETE, PLACE CONCRETE IN COMPLIANCE WITH ACI 305.

CP-8 PROVIDE CONCRETE MIX DESIGNS AND DELIVER CONCRETE IN ACCORDANCE WITH ASTM C94.

CP-9 PROVIDE CONCRETE SLAB FINISHES THAT CONFORM TO THE ARCHITECTURAL REQUIREMENTS OF THE PROJECT. FOLLOW PROCEDURE CONTAINED IN PARAGRAPH 5.3.4 OF ACI 301.

JW JOINTS AND WATERPROOFING JW-1 PROVIDE CONTINUOUS WATERSTOPS, AT EACH CONSTRUCTION JOINT OF ANY CONCRETE ELEMENT EXPOSED TO

SOIL OR WATER. AT ALL JOINTS CONTAINING WATERSTOPS, INTENTIONALLY ROUGHEN CONCRETE TO 1/4" AMPLITUDE SEE CIVIL DRAWINGS FOR ADDITIONAL REQUIREMENTS.

ARCHITECTURE   SURVEYING	2022 EQIP WASTE STORAGE FACILITY
ULEVARD, BARABOO WI 53913	BROOKS FARMS DAIRY, LLC
ISA Professional Services. Inc.	WAUPACA COUNTY, WI

ENGINEERING FUNDING | F

1230 SOUTH BC

MSA 颜

# STRUCTURAL SPECIFICATION SHEET

PROJECT NO. 21720000

SHEET S104

## **GENERAL NOTES**

- Α. SUPPORTING A BEARING PRESSURE OF 3000 PSF & A SUBGRADE MODULUS OF 200 PCI, COMPACTED GRANULAR SUBBASE SHALL BE MINIMUM 6" THICK OF CLEAN SAND OR 3/4" CRUSHED STONE WITH FINES. PROVIDE ADDITIONAL COMPACTED GRANULAR SUBBASE UP TO 10" THICK SHOULD SUBGRADE
- JOINTS BY PROPER INSTALLATION AND DETAILING OF WATERSTOPS. CONCRETE SHALL REACH 28-DAY COMPRESSIVE STRENGTH PRIOR TO D.
- BACKFILL
- REINFORCEMENT, WHERE POSSIBLE. PROVIDE ADDITIONAL DIAGONAL REINFORCING AROUND ALL OPENINGS AND PENETRATIONS THROUGH WALLS AND SLABS - SEE OPENING DETAIL 5/S303

- DESIGN (ACI 318 COMPLIANT) DOES NOT MEET THE REQUIREMENTS OF "LIQUID TIGHT" CRITERIA, WHICH REQUIRES ADDITIONAL LEVELS OF PROTECTION FOR GEOLOGIC CONCERNS, GROUNDWATER RESOURCES
- EMPTY TANK, FULL LIQUID WITH NO BACKFILL, AND STACKED FEED
- BUOYANCY. MAINTAIN GROUNDWATER TABLE BELOW THE TOP OF THE

- SURCHARGE
- SAND-LADEN

(HEIGHT OF SOIL 13'-0", ASSUMING UNSATURATED SAND BACKFILL)

(HEIGHT OF MANURE 16'-0")

(HEIGHT OF SOIL 7'-0", ASSUMING UNSATURATED CLAY/SILT BACKFILL)

(HEIGHT OF MANURE 16'-0")

RETAINING WALLS WITH RETAINED FEED STORAGE & IMPACT LOAD (HEIGHT OF SOIL 7'-0", ASSUMING OF UNSATURATED SAND BACKFILL) (IMPACT LOAD AT 11'-6" ABOVE TOF, ACROSS 5'-9" OF WALL WIDTH)









PROJECT NO 21720000

SHEET S303